

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location. NE SE SW
250' EL 1070 SL SW₂

DEEPENING RECORD.


Sec. 15 T. 26 R. 2E

Casing Record.

County Sedgwick.

20" 10" Farm. Wm. Brown
15 1/2" 8 8 1/2" Company. Shell Petroleum Corp.
12 1/2" 88 65/8" Contr. Noble & Olson.
12 1/2" 53/16" Comm. 10-14-29

No. 3



Comp. 11-11-29

Total Depth. 3205 Shot Quarts Between.

Correspondence Regarding This Well Should Be Referred To.

Elevation.

Figures Indicate Bottom of Formations.
Date Issued. 9-3-32

Initial Production. Swabbed
224 B.O & 121 B.Wtr O.T.D. 2893
New Prod- Pump 410 B.O. 24 hrs.
T.D. 3205

Formation	Depth	Formation	Depth.
surface	88	2889-91 300' oil in one hour.	
shale shells	364	2891-93 Increased to 700' 2 hrs.	
broken shale lime	552	2889-93 Pay 1250 oil in 6 hours.	
shale lime	871		
shale	1040	85/8 casing 2865	
shale lime shells	1441	7" casing 2888	
broken lime	1591		
shale lime shells	1817	<u>SAND RECORD.</u>	
broken lime shale	1973	Chat	2889-2893
broken lime	1983	Pay	2889-2893
shale	2101		
broken lime	2141	<u>DEEPENING RECORD.</u>	
lime	2211	Old T.D.	2893.
broken lime	2249		
shale	2279		
broken lime	2307	Comm. 6-29-32	Comp. 8-11-32.
lime	2426		
broken lime	2458	Production. Pump 410 B.C & No. water 24	hours.
lime	2489		
broken lime	2524	chat	2920
lime	2565	chat and lime	2940
shale broken lime	2666	chat	3002
broken lime	2696	lime	3010
shale shells	2734	lime hard	3040
broken lime	2762	lime	3145
shale	2800	shale	3173
broken lime shale	2871	3173 equals 3176 Correction.	
shale green yellow	2876	Top of shale 3148.	
shale green red	2879	shale	3193 1/2
lime brown	2881	shale	3202
shale yellow S.L.M.	2888	bailing water. Top trenton 3202.	
lime chat blk	2889	Oil 3202-05. 1600' oil - 1 hr at 4:30 P.M.	
chat	2893	2300' oil 1 1/2 hrs at 5 P.M.	
		Hole full oil 2 hours & 10 Min. ran	
		bailer 3 times no water HFW oil no wtr	
		chert and brown lime	3205
		Pump 410 oil & no water 24 hrs.	
		Pump 387 1/2 oil no water 24 hours.	
		T.D.	
		7" from 2997 UR3183 UR 3193 1/2	