

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG., WICHITA, KANSAS.

Location Block 7 Lot 17  
SW NW SE SW

Sec. 15 T. 26 R. 2E

Casing Record

County- Sedgwick

10" 2530 Farm-Community No. 1  
20" 93 8 1/4" 2722 Company- Shell Petr. Corp.  
15 1/2" 820 65/8" 2910 Contr.- R.O. Hawkins  
12 1/2" 1463 53/16" Comm.- 5-11-29 Comp.- 7-1-29  
Total Depth 2918 Shot Quarts Between  
Correspondence Regarding This Well Should Be Referred to



Elevation

Figures Indicate Bottom of Formations.  
Date Issued, 7-27-29

Initial Production  
1555 1/2 19 hrs.

Formation	Depth	Formation	Depth	Formation	Depth
clay	20	red rock	1075	shale	1775
shale	86	sdv lime	1090	lime	1780
gyp-lime	115	1 BW 1075-90		shale	1785
shale	135	shale	1135	lime	1800
lime	145	sdv lime	1145	blk shale	1810
shale	158	shale	1155	lime	1815
lime	170	shale	1175	shale	1850
lime-gyp	225	carrying 8 BW		lime	1880
shale	250	at 1165		shale	1885
red rock	260	lime	1180	lime	1910
shale	290	shale	1200	blk shale	1915
sdv shale	310	lime-shale	1225	shale	1920
red rock	325	lime	1235	lime	1930
shale-gyp	335	shale	1250	shale	1985
missing	380	lime	1260	shale	2125
lime-gyp	425	shale	1270	lime	2140
gyp-rock	465	lime	1275	shale	2168
shale	495	shale	1280	lime	2180
lime	500	lime	1288	shale	2220
gyp-shale	540	shale	1293	lime	2225
sdv lime	550	lime	1297	shale	2250
Show water	540-60	shale	1430	lime	2320
shale	570	lime	1438	shale	2330
red rock	580	sdv lime	1443	lime	2345
shale	595	sand HFW	1450	shale	2375
shale	620	shale	1455	lime	2405
gyp-lime	625	water sand	1463	shale	2480
1/2 BW/hr	625-30	lime	1465	lime	2485
shale	655	shale	1540	sdv shale	2500
red rock	660	sdv shale	1580	lime	2540
lime	675	shale	1600	sdv lime	2550
shale	715	sdv shale	1615	lime	2582
lime	725	1 1/2 BW/hr at 1615		blk shale	2590
shale	750	shale	1630	lime	2620
lime	759	lime	1645	shale	2724
shale	760	shale	1710	lime	2730
lime	765	sdv lime	1715	shale	2665
shale	785	1 BW/hr 1715		red rock	2666
lime	795	shale	1745	shale	2825
shale	800	lime	1750	lime	2830
lime	805			shale	2870
sand 4 BW/hr	815			lime	2880
shale	820			shale	2900
lime	822			lime	2914
lime	835			lime-chat	2918
slate	840			TD	2918
lime	845				
shale	890				
4 BW/hr	880-90				
shale	910				
lime	915				
shale	960				
lime	965				
shale	995				
red rock	1000				
shale	1020				
red rock	1030				
shale	1035				
red rock	1040				
lime	1045				
sdv lime	1065				
3 BW/hr					

Corrected pay 2914-18  
Filled up and flowed in 1 1/2 hours.  
First 5 1/2 hours flowed 581 barrels.  
Following 24 hours flowed 1555 1/2 bbls.  
(4 1/2 hours down for tankage)