


15-26-2E

**KANSAS DRILLERS LOG**

State Geological Survey  
WICHITA, BRANCH

S. 15 T. 26 R. 2 <sup>E</sup><sub>W</sub>  
Loc. NW NE SE  
County Sedgwick

API No. 15 — Sedgwick — 173-2009  
County Number  
Operator United Pet. Co.  
Address 214 Sage Court, Wichita, Kansas  
Well No. #1 Lease Name Fischer  
Footage Location  
feet from (N) (S) line feet from (E) (W) line  
Principal Contractor R. H. & Jones Geologist Carl Brandt  
Spud Date 1/22/72 Total Depth 3342 P.B.T.D.  
Date Completed 2/2/72 Oil Purchaser Shelby Oil Company



Locate well correctly  
Elev.: Gr. 1409  
DF 1414 KB 1414

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface		8 5/8	29 #	205		185	
production	7 7/8	5 1/2	14 #	3341		100	

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
	<u>none</u>		<u>3</u>		
<b>TUBING RECORD</b>			<u>stalled</u>		<u>3329-3330</u>
Size	Setting depth	Packer set at			
<u>2 3/8" O.D.</u>	<u>3320</u>				

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
<u>none</u>	

**INITIAL PRODUCTION**

Date of first production 2/24/72 Producing method (flowing, pumping, gas lift, etc.) pumping  
 RATE OF PRODUCTION PER 24 HOURS  
 Oil 24 bbls. Gas — MCF Water 5 bbls. Gas-oil ratio — CFPB  
 Disposition of gas (vented, used on lease or sold) \_\_\_\_\_ Producing interval (s) \_\_\_\_\_

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator *United Petroleum Company*

Well No. *1* Lease Name *Fischer* DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: *oil*

S *15* T *26* R *2* E *W* *Sedgewick County*


**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.




*Ray Steholl*  
Signature

*partner*  
Title

*4/12/73*  
Date

DEC 15 1972

CARBERRY-JONES, INC.  
 WICHITA, KANSAS  
 DRILLERS' WELL LOG



FISCHER #1  
 NW NE SE, Section 15-26-2E,  
 Sedgwick County, Kansas

Commenced: January 21, 1972  
 Completed: February 2, 1972

1414 KB  
 25 BOPD

OPERATOR: United Petroleum Company

Depth	Formation	Remarks
From To		
0 00	Surface clay	Ran 9 jts of used 8 5/8" csg. Set @
63 211	Lime	205' w/125 sks 3% CC
211 280	Shale-lime	P.D. 6 PM 1/21/72. Cement Circ.
280 799	Lime-shale	Job by United
799 2275	Shale-lime	Centralizer 5' below collar on shoe joint.
2275 2924	Lime	
2924 3073	Chat	
3073 3344	Lime	
3344 TD		Ran 108 jts of used 5 1/2" csg. set @ 3341'. 1' off bottom cemented w/ 100 sks 60/40 Fosmix Latex P.D. 8:15 PM 2/2/72 Job by United

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled in the NW NE SE, Section 15-26-2E, Sedgwick County, Kansas, to the best of my knowledge and belief.

*James S. Sutton II*  
 James S. Sutton, II.

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Before me, the undersigned, a Notary Public within and for said County and State, on this 7th day of February, 1972, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day last above written.



*Marjorie Hall*  
 Marjorie Hall, Notary Public

- SMP TOPS
- KC 2449
- BNC 2611
- Miss ch 2914
- KH 3123
- Hun 3197
- Viola 3224
- Simp Del 3243
- Simp sd 3323
- Arb 3333
- RTD 3342

