


Location SE NE SE
942' NL 330' EL SE 1/4

Casing Record

County- Sedgwick OCT 21 1929

10" Farm- K.F. Fischer No. 2
20" 8 1/2" 2880 Company- Shell Petr. Corp.
15 1/2" 86' 65/8" Contr.- Noble & Olson
12 1/2" 53/16" 3198 Comm.- 7-22-29 Comp.- 9-28-29
Total Depth 3200 Shot Quarts Between
Correspondence Regarding This Well Should Be Referred to



Elevation 1476

Figures Indicate Bottom of Formations.
Date Issued. 10-19-29

Initial Production SW. 422 1/2
bbls. oil 1st 24 hrs.

Formation	Depth
clay yellow	70
wtr sand	75
brkn lime	80
shale & rock	86
surface rock	96
brkn lime & shale	162
lime shells & shale	330
sdv lime	355
shale	460
lime	470
shale	535
sand	575
shale	600
sdv lime	625
sdv shale	915
sdv lime	971
red beds	983
sdv lime	1033
sand	1063
sand & shale	1140
shale sticky	1226
sdv lime & shale	1303
shale	1487
brkn shale & lime	1507
shale sticky	1555
sdv shale & lime	1603
brkn sdv shale	1613
lime	1638
brkn lime	1668
lime & shale	1738
variegated shale	1753
lime	1788
brkn shale & shells	1814
brkn lime & shale	1830
shale	1904
shale & lime shells	1924
lime	1974
shale	1984
shale & lime	2047
shale sticky	2107
shale & brkn lime	2120
lime	2144
shale	2156
shale & lime	2183
lime	2195
brkn lime & shale	2200
shale sticky	2263
lime	2378
brkn lime & shale	2386
shale & lime shells	2396
shale sticky	2430
shale & lime shells	2451
lime	2456
brkn lime	2462
lime shells	2489
lime	2504
shale	2524
lime	2530
shale	2546
lime	2561
brkn lime & red rock	2570
lime	2585
brkn lime & shale	2596
shale	2600

Formation	Depth
lime	2620
shale sticky	2670
lime	2700
shale & lime shells	2710
brkn lime	2745
shale & lime	2785
brkn lime & shale	2814
shale	2837
lime	2860
shale	2885
variegated shale	2900
chat & variegated shale	2917
red rock Top chat	2928
chat	2964
chat coarse small amount of lime	2975
chat lime	2995
lime	3155
shale blk	3198
lime some chert	3198-99
Total Depth	3200

Top chat 2928, drilled to 2929,
swabbed five bbls. oil & 150
wtr in seven hrs, 8-25-29.
8-26-29 22 1/2 oil 196 wtr 21hrs.sw
9-3-29 533 oil 185 wtr 6 hrs.sw

SANDS

2928-2995 chat Pay 2928-31
3198-3200 Trenton lime
Pay 3198-3200'.

7" csg. set at 2921 & U.R. 3108'.