

39059

UNION NATIONAL BANK BLDG., WICHITA, KANSAS.

Location NE SE SE.

DEEPENING RECORD.

Sec. 16 T. 26 R. 2E.

330' EL 990' SL SE/4

Casing Record

7" 3101 10"

20" 85/8 2916

15" 118 65/8"

12" 53/16" 3208

Total Depth 3240

Correspondence Regarding This Well Should Be Referred to

Farm- K. F. Fischer

Company- Shell Petroleum Corp.

Contr.- Noble & Olson.

Comm.- 1/25/30.

Shot

Quarts Between

County- Sedgwick.

No. 6

Comp.- 3/6/30.



Elevation

Figures Indicate Bottom of Formations.

Initial Production 699 bbls.

Date Issued. 9-7-35.

Gravity 39.4

Formation	Depth	Formation	Depth
clay	40	lime	2800
sand gravel	78	sticky shale	2820
brkn lime	158	brkn lime	2841
shale & shells	305	lime	2900
shale & lime shells	507	shale	2906
sand	527	brkn lime	2917
shale & shells	781	Steel line correction	2915
shale	1100	chat	2925
lime	1116	Water 1550', 250' oil at 2915'	
shale	1234	chatty lime carrying HFV	2940
sdv shale	1260	lime carrying HFV	2950
lime	1264	sdv lime carrying HFV	2957
shale & shells	1376	lime carrying HFV	3050
shale	1380	shale white	3055
lime	1450	sdv shale white	3075
shale	1651	lime	3140
brkn lime	1665	brown lime	3153
shale & shells	1687	shale black	3194
brkn lime	1800	S. L. C.	3196 1/2
shale	1854	shale black	3208 1/2
shale & lime shells	1875	lime HF Oil	3209 1/2
shale	1944		
brkn shale	2000	Total Depth	3209 1/2
lime	2030		
shale	2090		
brkn lime	2100		
sdv shale	2121		
shale	2220		
lime	2303		
brkn lime	2312		
shale hrd	2330		
sticky shale	2350		
shale hrd	2377		
lime	2430		
shale	2490		
lime	2530		
shale	2548		
lime	2598		
brkn lime	2660		
sticky shale	2704		
lime	2713		
brkn lime	2735		
sticky shale	2765		

OVER OVER

K. F. Fischer No. 6
Shell Petro.
15-26-2E.
DEEPENING RECORD.

118868
118871

Old T.D. 3209 $\frac{1}{2}$
Comm. 7-20-35 Comp. 8-16-35.
Prod. Swabbed 320 bbls oil and
no water 24 hours.
lime 3209 $\frac{1}{2}$ 3214
lime 3243
sand 3276
sand 3295
shale 3296
shale 3303
sand 3307
shale 3311
sdy shale 3320
sdy shale 3325
sand 3327
sand 3328
shale green 3331
shale green and sand 3340
hole filled up 1700' oil 2 hours
Swabbed 270 bbls oil and no wtr
12 $\frac{1}{2}$ hours.
Swabbed 235 bbls oil and no water
12 $\frac{1}{2}$ hours.
8-20-35 Swabbed 82 $\frac{1}{2}$ bbls oil 3 hours.
8-21-35 swabbed 320 bbls oil and no
water 24 hours.
Total Depth. Oil pay 3323-228 1700' oil 2 hours.
7" casing. 3317'