

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 Union National Bank Building, Wichita, Kansas.

SHELL PETROLEUM CORP.
 K. F. Fischer No. 10

SEC. 15 T. 26 R. 2E.
 SE NE SW SE
 1055' fr WL 865' fr SL

Total Depth. 3204
 Comm. 6-8-35 Comp. 7-9-35
 shot or Treated. 1000 gal acid.
 Contractor.
 Issued. 7-27-35.

County. Sedgwick.



Elevation.

CASING.

133/8" 91' 7" 3181'

Production, 1016 B. 72 Hrs.
 Pumping.

Figures Indicate Bottom of Formations.

soil	75	chat hard and sharp	3022
lime shells	91	lime	3031
anhydrite	140	lime hard	3056
anhydrite & shale	197	lime	3089
shale and shells	375	lime brown	3108
shale and lime	461	shale	3150
shale and shells	573	3150 equals 3154 S.L.C.	
lime and shale	745	shale	3181
lime	843	shell lime hard	3182
shale and shells	1267	standardizing.	
shale and shells	1416	shale blk	3202
lime	1442	chert	3202 1/2"
shale and lime	1464	dolomite show of oil	3204 Total Depth.
lime	1478	hole filled up 860' of oil and	
broken lime and shale	1525	260' of water in 6 hours at	
shale	1540	3204.	
shale & lime shells	1638		
lime and shale	1766	7-10-35. Swabbed 115 bbls oil and	
shale and shells	1861	65 bbls water in 18 hours.	
lime and shale	1973		
shale & lime shells	2067	7-13-35. Swabbed 445 bbls oil and	
lime	2136	460 bbls water in 10 1/2 hours.	
lime and shale	2264		
lime	2346		
lime	2394	339 B.O. and 1230 B.W. 3 day	
lime and shale	2431	average (pumping)	
shale and shells	2497		
lime and shale	2607		
lime	2646		
broken lime	2750		
lime and shale	2841		
lime and shale	2882		
Var. col shale	2899		
chat soft	2910		
chat hard	2913		
chat soft	2930		
chat soft	2934		
chat hard	2950		
chat	3002		