

15-26-2E


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - SHAWVER-GRAHAM, INC.
Farm - Lygrisse "B" No. 2

SEC. 15 T. 26 R. 2E
NE NW SW

Total Depth. 3323'
Comm. 3-29-49 Comp. 4-30-49
Shot or Treated.
Contractor.
Issued. 6-11-49

County. Sedgwick
KANSAS



Elevation. 1388 Ind

Production. Dry

CASING:
8-5/8" 110' Cem. W/85 Sx.
4-1/2" 3290' Cem. W/125 Sx.

Figures Indicate Bottom of Formations.

clay	40
clay & shells	60
shells & shale	110
lime & shale	740
shale & shells	1470
shale, lime & iron	2655
shale & lime	2891
chat	2919
chat & chert	2950
lime & chert	3090
lime & shale	3195
Top iola	3239
lime	3243
Simpson Sand	3270
sand RTD	3275
shale	3292
sand	3317
sand & shale	3319
sand	3323
Total Depth	

Top Viola	3099 3195
KANSAS CITY	2425
MISSISSIPPI	2891
SIMPSON	3243
SIMPSON SAND	3275