

UNION NATIONAL BANK BLDG., WICHITA, KANSAS.

Location SE c SE SW SW (lot 16, block 11)
165' SL 1077' WL SW/4

Sec. 15 T. 26 R. 2E **37910**

Casing Record

County - Sedgwick

10" 1578' 4" Farm - Scharr or Boque (owner) No. /
20" 8" 2560' Company - Graham Drlg. Co.
15 1/8" 113' 65/8" 2910' 8" Contr. -
12 3/8" 1077' 7' 53/16" Comm. - 8-14-29 Comp. - 11-20-29
Total Depth 2939 Shot Quarts Between
Correspondence Regarding This Well Should Be Referred to



Elevation

Figures Indicate Bottom of Formations.

Initial Production 136 bbls.

Date Issued. 12-7-29

Formation	Depth	Formation	Depth	Formation	Depth
soil	5	red rock	1000	shale blue	1870
clay yellow	65	shale	1020	lime	1900
shale blue	75	red rock	1030	slate blk	1920
lime 2 1/2 BW	78	shale	1035	shale blue 1 BW	1925
shale blue	95	red rock	1045	lime	1940
sand HFW 105'	107	lime	1050	slate wh	1995
shale blue	120	shale blue	1060	shale	2080
shale drk	125	brkn line 10 BWPH	1070	shale blue	2120
lime hrd	145	red rock	1075	lime	2150
shale	150	shale blue	1080	shale lgt	2165
lime	160	shale	1085	lime	2190
shale	175	shale drk	1105	shale lgt	2225
lime	180	shale	1115	shale lgt	2235
shale blue	192	shale	1160	lime	2345
sdv lime	197	lime	1170	shale drk	2350
shale blue	203	shale	1180	shale	2360
lime	223	lime	1185	lime	2395
shale blue	243	shale drk	1195	shale blue	2470
red rock	255	shale lgt	1215	lime	2485
shale blue	265	shale blk	1220	shale	2495
lime	275	lime	1240	lime	2550
shale blue	290	shale lgt	1255	wtr sand	2570
lime	300	shale lgt	1260	HFW 2550-70'	
shale blue	310	lime	1285	lime	2592
red rock	315	shale	1300	shale	2597
shale	325	lime	1305	lime	2610
lime	360	shale	1315	shale	2613
shale blue	375	lime	1320	lime lgt	2620
lime	420	shale	1330	shale	2625
lime	465	lime	1335	lime	2653
shale blue	475	shale	1365	shale	2685
red rock	485	shale blue	1420	lime	2705
lime	495	lime	1455	shale	2715
shale	500	HFW 1435-50'		lime	2725
lime	505	lime	1470	shale	2760
shale	510	10 BW 1465'		slate blk	2771
shale blue	520	shale	1475	red rock	2774
lime	530	lime	1480	shale	2797
sand 2 BW	560	shale	1485	lime	2807
shale blue	570	lime	1495	slate blk	2825
red rock	580	shale blue	1500	brkn lime	2835
shale drk	590	shale	1515	lime	2845
lime	595	lime	1525	slate blk	2850
shale	630	shale	1545	lime	2865
sand	640	lime	1549	shale	2870
red rock	645	shale lgt	1562	lgt shale	2883
shale blue	680	sdv lime	1575	lime	2888
shale	695	sdv lime	1579	shale	2905
lime	710	sdv lime	1582	Various shales	2925
shale	740	shale blue	1595	Various colored	
lime	750	lime	1597	shales	2933
shale	775	slate blk	1625	red rock	2938
lime	810	lime	1637	chat Oil	2939
shale	820	shale blue	1655		
lime	850	lime	1690	Total Depth	2939
shale	855	1 BW 1675-90'			
lime 2 BWPH	870	shale	1710	Measurement corrected	
shale	875	lime	1715	to 2913' -- 6"	
lime	900	shale blue	1740	Set 2912' of tubing rods	
shale	905	lime	1745	off bottom 18".	
lime	915	shale blue	1765	P. O.	
shale	935	lime	1795	Line 2939 - 3012 T.D.	
shale blue	945	slate blue	1805		
lime	950	shale blue	1825		
slate blk	990	lime	1860		

3-18-31-28