



OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

January 8, 1981

Ronald Burris Oil Company, Inc.
Box 222
Iola, Kansas 66749

Gentlemen:

Attached hereto are the results of tests run on the rotary core taken from the Vanetta Lease, Well No. 1, located 156' East of the West Line and 155' South of the North Line in Section 17, T-26S, R-21E in Allen County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and submitted to our laboratory on December 30, 1980.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Sanford A. Michel

SAM/kas

5 c to Iola, Kansas

- REGISTERED ENGINEERS -

CORE ANALYSIS - WATER ANALYSIS - REPRESSURING ENGINEERING - SURVEYING & MAPPING - PROPERTY EVALUATION & OPERATION

OILFIELD RESEARCH LABORATORIES

LOG

Name Ronald Burris Oil Co., Inc. Lease Vanetta Well No. 1

<u>Depth Interval,</u> <u>Feet</u>	<u>Description</u>
696.0 - 696.9	Grayish light brown shaly sandstone.
696.9 - 698.0	Brown sandstone.
698.0 - 699.8	Light brown shaly sandstone.
699.8 - 700.7	Brown slightly shaly sandstone.
700.7 - 706.0	Brown sandstone.
706.0 - 706.6	Grayish light brown very shaly sandstone.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Ronald Burris Oil Co., Inc.

Vanetta

1

Company _____ Lease _____ Well No. _____

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	696.5	14.0	28	68	96	304	5.2
2	697.5	21.0	53	33	86	864	20.
3	698.5	17.4	31	62	93	418	0.37
4	699.5	18.2	41	32	73	579	1.5
5	700.5	15.7	42	42	84	512	8.3
6	701.4	15.8	23	52	75	282	11.
7	702.5	19.2	37	32	69	551	18.
8	703.6	16.4	39	39	78	496	37.
9	704.5	18.6	47	29	76	678	30.
10	705.5	14.2	10	81	91	110	24.
11	706.4	5.0	30	61	91	116	Imp.