



OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

January 13, 1981

Ronald Burris Oil Company, Inc.
Box 222
Iola, Kansas 66749

Gentlemen:

Attached hereto are the results of tests run on the rotary core taken from the Vanetta Lease, Well No. 2, located in Section 17, T-26S, R-21E, in Allen County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and submitted to our laboratory on January 5, 1981.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Sanford A. Michel

SAM/kas

5 c to Iola, Kansas

- REGISTERED ENGINEERS -

CORE ANALYSIS - WATER ANALYSIS - REPRESSURING ENGINEERING - SURVEYING & MAPPING - PROPERTY EVALUATION & OPERATION

OILFIELD RESEARCH LABORATORIES

LOG

Name Ronald Burris Oil Company, Inc. Lease Vanetta Well No. 2

<u>Depth Interval,</u> <u>Feet</u>	<u>Description</u>
721.0 - 724.0	<u>BARTLESVILLE SAND</u> Brown and gray laminated sandstone and shale.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Ronald Burris Oil

Company Company, Inc. Lease Vanetta Well No. 2

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	721.2	20.1	40	18	58	624	4.1
2	722.5	15.0	46	16	62	535	9.4
3	723.4	15.5	38	44	82	457	Imp.