

OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

July 26, 1980

KLI Petroleum Corporation
808 Southeast Sixth
Evansville, Indiana 74048

Gentlemen:


Attached hereto are the results of tests run on the rotary core taken from the Guy Shirley Lease, Well No. K-3, located 300' North of the South Line, 1,000' East of the West Line, in Section 29, T-26S, R-21E, Allen County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and submitted to our laboratory on June 25, 1980.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES


Sanford A. Michel

SAM/tem

5 c to Evansville, Indiana

OILFIELD RESEARCH LABORATORIES

LOG

Name KLI Petroleum Corp. Lease Guy Shirley Well No. K-3

Depth Interval,
Feet

Description

BARTLESVILLE SAND

678.5 - 679.0

Hard gray limestone.

679.0 - 680.0

Hard brown very calcareous sandstone.

680.0 - 680.4

Hard gray calcareous sandstone.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Company KLI Petroleum Corp. Lease Guy Shirley Well No. K-3

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	679.1	13.8	36	23	59	385	0.24
2	679.8	12.2	49	29	78	464	Imp.