

# OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

July 7, 1982

Ashdan Oil  
c/o Advanced Systems Homes  
Box 45A  
Chanute, Kansas 66720

Gentlemen:

Attached hereto are the results of tests run on the rotary core taken from the Daniels Lease, Well No. 26, located in Section 9, T-26S, R-21E, in Allen County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and was submitted to our laboratory on July 6, 1982.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES



Sanford A. Michel

SAM/dlb

5 c to Chanute, Kansas

OILFIELD RESEARCH LABORATORIES

LOG

Name Ashdan Oil Lease Daniels Well No. 26

Depth Interval,  
Feet                      Description

BARTLESVILLE SAND

704.0 - 706.0              Brown sandstone with scattered gray shale partings.

706.0 - 707.0              Brown sandstone.

707.0 - 707.2              Coal.

**Oilfield Research Laboratories**

**RESULTS OF SATURATION & PERMEABILITY TESTS**

**TABLE 1**

Company Ashdan Oil Lease Daniels Well No. 26

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbla. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	704.6	19.3	36	22	58	539	78.
2	705.3	18.3	30	34	64	426	13.
3	706.6	19.6	38	36	74	578	84.