



OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

March 12, 1982

Inexco Oil Company
R R # 2, Box 3
Moran, Kansas 66755

Gentlemen:

Attached hereto are the results of tests run on the rotary core taken from the Campbell Lease, Well No. F-15, located in Section 18, T-26S, R-21E, in Allen County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and was submitted to our laboratory on March 12, 1982.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Sanford A. Michel

SAM/kas

3 c to Moran, Kansas
2 c to Oklahoma City, Oklahoma

OILFIELD RESEARCH LABORATORIES

LOG

Name Inexco Oil Company Lease Campbell Well No. F-15

<u>Depth Interval, Feet</u>	<u>Description</u>
	<u>BARTLESVILLE SAND</u>
743.0 - 743.5	Brownish black shaly sandstone.
743.5 - 745.6	Gray and brownish black laminated shale and sandstone.
745.6 - 750.7	Brownish black sandstone.
750.7 - 751.2	Brownish black sandstone with gray shale partings.
751.2 - 752.0	Gray shale.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Company Inexco Oil Company Lease Campbell Well No. F-15

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	743.3	13.7	40	55	95	425	2.3
2	744.6	14.4	28	60	88	313	0.18
3	745.2	16.1	49	42	91	612	0.28
4	746.5	18.7	55	20	75	798	203.
5	748.3	19.8	46	32	78	707	259.
6	749.7	20.4	40	46	86	633	203.
7	750.8	18.3	52	34	86	738	31.