

Nelson #RW-15

Page 6

July 22, 1998:

Set up Company pulling unit. Ran 1" wash string with jet bit. Washed to bottom at 725'. Pulled up bit and dropped 1/2" ball. Jetted perforations with 600 lbs. pressure at a depth of 680' to 696'. Spotted 50 gallons 28% HCl acid, one gallon Goldtreat, one gallon ESA-96, one quart ESA-91, and one pint ESA-50 on perforations and displaced with four barrels injection fluid using pump truck. Shut well in.

August 14, 1998:

Spotted 50 gallons 28% HCL acid, one gallon Goldtreat, one gallon ESA-96, one quart ESA-91, and one pint ESA-50 over perforations and pulled 1" Hooked up to pump truck and displaced with six barrels injection fluid and shut in; will hook up at a later date.

August 31, 1998:

Well reactivated.

September 2, 1998:

61 bbls. @ 320 lbs.

September 3, 1998:

65 bbls. @ 370 lbs.