

NELSON REMEDIAL WORK POSSIBILITIES

10/27/97

<u>Well No.</u>	<u>Gross Sand</u>	<u>Net Sand</u>	<u>Floodable Sand</u>	<u>Perfs.</u>
KW-8 (B-2)	12.0 (est.)	12.0 (est.)	10.0 (est.)	638-45 & 648-62
(B-3)	0	0	0	665-73 & 678-88
				698-701 & 705-08

Seating Nipple: None
Fraced: No Data

Casing: 2 7/8"

Logger T.D.: 726'

Recommendations:

Using 1" pipe, wash to 665-70. Shut-in overnight. Spot acid and chemicals at 665-70. Pull 1". Return to injection.

Further discussion: Temp survey indicates water entering formation from 660' to T.D. This is below the bottom of B-2 Zone at 660'. Attempt to shut off perfs. below 660'????