

Nelson #KW-10

Page 9

November 13, 1998:

Set up Company pulling unit. Ran 1" pipe and jet bit to 672' and washed well. Dropped 1/2" ball and jetted perforations from 672'-652', recovering iron sulfide and scale. Set pipe back down at 672'. Spotted first treatment of 50 gallons 28% acid, one gallon ESA-96, one gallon Goldtreat, one pint ESA-50, and one quart ESA-91. Displaced with four barrels injection water and shut-in over weekend.

November 16, 1998:

Repeated above treatment. Pulled 1" and jet bit. Hooked up to injection system.

November 18, 1998:

56 bbls. @ 460 PSI

November 19, 1998:

36 bbls. @ 520 PSI