

Nelson #H-5

Page 4

July 10, 1998:

Set up Company pulling unit. Ran 2" jet bit and washed to bottom of 694'. Pulled 1" pipe to jet perforations after dropping 1/2" ball. Jetted perforations at depth of 662'-671'. Spotted 50 gallons of acid, one gallon ESA-96, one gallon Goldtreat, one pint ESA-50, and one quart ESA-91 on perforations. Chased with three barrels injection water. Pulled pipe. Put on new 2" Bolt packer with 40' tail pipe and ran to depth of 629'. Set in tension and clamped off. Resumed normal injection.

NOTE: Well is old producer. Has hole in 2" casing. Must put any put any acid or chemical down 1" with packer only.

July 11, 1998:

35 bbls. @ 380 lbs.

July 12, 1998:

40 bbls. @ 390 lbs.

July 13, 1998:

51 bbls. @ 410 lbs.