

NELSON #K-36

Location: 2210' SNL & 165' WEL Elevation: 1066.3'
 Sec. 21, T26S, R21E Seating Nipple @ 659.5'
 Allen County, Kansas

Perforations: 626'-630'; 647'-653'; 676'-688'

April 18, 1995:

Ran steel measuring line to T.D. of 682'.

November 24, 1998:

Using A & A Well Service's pulling unit, ran 1" pipe. Hit hard spot at 690'; washed to 702'.

Using A & A Well Service's wash truck, pumped 16 sacks of cement down 1" pipe and circulated to surface. Pulled all but 200' of 1". Pumped four sacks of cement and circulated to surface. Pulled 1" pipe. Filled 2 7/8" casing with cement. Installed a 2 7/8" to 1" swage. Connected 1" high pressure hose to wellhead and squeezed three sacks of cement; pressured up to 575 pounds. Shut-in 2" valve.

Washed up equipment and moved off.