

NELSON #K-35

Location: 1810' SNL & 165' WEL T.D.: 760'  
SW, Sec. 21, T26S, R21E P.B.T.D.: 717'  
Allen County, KS  
Elevation: 1066.2' 2 7/8" @ 690'  
Perforations: 6 holes from 622'-627'  
4 holes from 631'-634'  
7 holes from 652'-658'  
Seating Nipple @ 629'  
7" surface casing to 49'

October 6, 1995:

Ran steel line measure to 679'. Shut-in pressure, 18 PSI. Water at surface.

November 23, 1998:

Using A & A Well Service's pulling unit, ran 1" pipe to 655'. Hit soft bottom.

Using A & A Well Service's wash truck, washed 1" pipe to 675'. Pumped 17 sacks cement. Pulled all but 200' and circulated cement to surface. Pulled 1". Connected 1" hose to 2 7/8" swage. Squeezed two sacks of cement; pressured to 700 PSI. Shut-in 2" wellhead.

Washed up and moved off.