

Ind . . . 31

18-26-22E

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5512 EXPIRATION DATE 8506

OPERATOR Riviera Drilling & Exploration API NO.

ADDRESS 899 Logan Street, Suite 101 COUNTY Bourbon

Denver, Colorado 80203 FIELD Wildcat

** CONTACT PERSON Ronald R. Retzlaff PROD. FORMATION N/A

PHONE (303) 863-8811

PURCHASER N/A LEASE J.K. Corporation

ADDRESS WELL NO. #9

WELL LOCATION

DRILLING N/A 1485 Ft. from East Line and

CONTRACTOR 2475 Ft. from South Line of

ADDRESS theSE (Qtr.) SEC18 TWP26 RGE22E.

PLUGGING Dowell WELL PLAT (Office Use Only)

CONTRACTOR Chanute, Kansas

ADDRESS

TOTAL DEPTH 800 Est. PBTD

SPUD DATE DATE COMPLETED 2/23/84

FEV: GR DF KB

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented DV Tool Used?

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

KCC
KCS ✓
SWD/REP
PLG.

A F F I D A V I T

Ronald R. Retzlaff, being of lawful age, hereby certifies

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Ronald R. Retzlaff (Signature)

(Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 9th day of April

335337

266-26-81

SIDE TWO

ACU-1 WELL HISTORY

OPERATOR Riviera Drlg. & Expl. LEASE J.K. Corp. 9

SEC. 18 TWP. 26 RGE. 22E

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; core intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Open Hole Well Plugged & Abandoned				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used		Depth interval treated
P & A with 50' plug on bottom, shut down, pull		
1" tubing to 350', cement to surface, using 110 sxs		
Class "A" cement, 21 lbs. D-46 antifoam, 200 lbs CaCl		
Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
N/A	N/A	N/A
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas
	N/A	N/A
Disposition of gas (vented, used on lease or sold)	Perforations	
N/A	N/A	

--	--	--	--	--

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used) N/A

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives

LINER RECORD N/A

PERFORATION RECORD N/A

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD N/A

Size	Setting depth	Packer set at



18-06-22E *Unid.*
 State Geological Survey
 WICHITA BRANCH

Riviera Drilling & Exploration Co.
 J.K. Corp. #9, 1485' FEL, 2475' FSL
 Sec. 18, T 26S, R 22E
 Bourbon Co., Ks.

Drill Contractor: Drill Energy, Inc.

API Number 15-011-21.190

Casing: 29'4"

Elevation: 1079'

Date Started: 5-28-81

Date Finished: 5-29-81

SAMPLE EXAMINATION

<u>Depth</u>	<u>Description</u>	<u>Depth</u>	<u>Description</u>
0-2	Overlay	255-273	Shale, gray
2-12	Broken Limestone & Clay	273-301	Limestone
12-35	Limestone	301-302	Coal
35-36	Shale, gray	302-307	Shale, gray
36-37	Limestone	307-340	Limestone
37-40	Shale, gray	340-368	Shale, gray
40-42	Limestone	368-372	Limestone
42-43	Shale, gray	372-380	Sand w/little limestone
43-77	Limestone	380-388	Shale, gray
77-86	Shale, gray	388-405	Limestone
86-89	Shale, dark gray	405-407	Limy Shale, dark gray
89-95	Shale, gray	407-409	Shale, black
95-100	Limestone	409-410	Shale, gray & clay
100-135	Shale, gray	410-415	Limestone
135-160	Sand	415-417	Shale, gray
160-196	Shale, gray	417-418	Limy Shale
196-199	Shale, black	418-420	Shale, black
199-202	Shale, gray & Clay	420-424	Shale, gray
202-208	Shale, gray & Shale, green	424-425	Limestone
208-242	Limestone	425-431	Sand
242-245	Shale, gray & green	431-435	Shaly Sand
245-255	Sand		

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 12 1983
 CONSERVATION DIVISION
 Wichita, Kansas

18-26-22E

State Geological Survey
WICHITA BRANCHK. Corp. #9, 18-26-22E
Bourbon Co., Ks.

SAMPLE EXAMINATION

<u>Depth</u>	<u>Description</u>	<u>Depth</u>	<u>Description</u>
435-436	Shale, gray and Clay	590-598	Sand
436-449	Shale, gray	598-600	Shaly Sand
449-450	Limestone	600-605	Shale, dark gray
450-486	Shale, gray	605-607	Shale, gray & Clay
486-487	Black Limestone	607-611	Shaly Sand, green
487-496	Shale, black	611-617	Shale, green
496-498	Shale, gray & Coal	617-622	Christmas Shale
498-500	Shale, gray & Clay	622-624	Shale, gray
500-518	Shale, dark	624-626	Sand
518-522	Brown Limestone	626-632	Shale, black
520-523	Shale, black	632-635	Shale, gray & Clay
523-525	Coal	635-645	Shale, gray
525-530	Shale, gray & Clay	645-651	Sand
530-535	Limy Shale	651-652	Shale, gray Limestone
535-538	Shale, gray	652-654	Limestone, brown
538-543	Shaly Sand	654-655	Shale, gray
543-544	Sand	655-660	Shale, gray & Clay
544-545	Shale, gray	660-661	Shale, black
545-546	Coal w/gray shale	661-668	Shale, gray
546-549	Shale, gray & Clay w/some Sandy Shale	668-670	Sand
549-551	Sand	670-672	Sandy Shale
551-565	Shale, gray	672-674	Shale, gray
565-574	Shaly Sand	674-680	Shale, gray and Brown Limestone
574-579	Shaly Sand (gas odor)	680-683	Sandy Shale
579-588	Shale, dark gray	683-685	Shale, Christmas
588-590	Shale, black	685-686	Shaly Sand

18-26-22E

State Geological Survey
WICHITA BRANCH

O.K. Corp. #9, 18-26-22E
Bourbon Co., Ks.

SAMPLE EXAMINATION

<u>Depth</u>	<u>Description</u>	<u>Depth</u>	<u>Description</u>
686-687	Shale, black	783-785	Coal
687-689	Shale, gray	785-786	Shale, dark
689-694	Sandy Shale	786-787	Sand (odor)
694-696	Shaly Sand	787-788	Chirt (odor & show)
696-706	Shale, dark w/little Limestone	788-790	Chirt (no odor or show)
706-710	Sand	790-795	Chirt (little show now and then)
710-711	Sand (little show & odor)	795-800	Limestone
711-712	Sand (no show or odor)		
712-718	Sand & Shale, gray		T.D. AT 800'
718-722	Sandy Shale		
722-727	Sandy Shale w/Limestone		
727-728	Coal		
728-731	Shale, gray		
731-747	Shale, dark & Limestone		
747-749	Shale, gray & Coal		
749-755	Sandy Shale, dark		
755-756	Shale, dark & gray		
756-768	Shale, dark		
768-770	Sandy Shale, dark		
770-771	Brown Limestone		
771-779	Shale, dark (trace of lime)		
779-781	Sandy Shale		
781-783	Shale, dark		