



12-98-92c

SIDE TWO

Operator Name American Shallow Development Lease Name Griffith Well # 27

Sec. 15 Twp. 26S Rge. 23  East  West County Bourbon

METHOD OF COMPLETION

Production Interval

Disposition of gas:  Vented  
 Sold  
 Used on Lease

Open Hole  Perforation  
 Other (Specify) Plugged

Dually Completed  
 Plugged

Drill Stem Tests Taken  Yes  No  
 Samples Sent to Geological Survey  Yes  No  
 Cores Taken  Yes  No

Formation Description  
 Log  Sample

	Top	Bottom
Soil	0	5
Lime (oil odor 30)	5	37
Shale	37	87
Lime (oil odor 90)	87	105
Shale	105	112
Lime	112	118
Shale	118	119
Coal	119	120
Shale	120	123
Sand (oil odor 125)(oil show 129)	123	155
Sandy Shale	155	180
Shale	180	204
Coal	204	205
Shale	205	259
Sandy Shale	259	268
Sand	268	271
Broken Sand	271	273
Sand (oil odor) (oil show 280)	273	308
Shale	308	350

Name Top Bottom

CASING RECORD  New  Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
Surface		7"	17%	24'	Common	10	Portland "A"
Production		4 1/2"	9%	347'	Common	45	Calc. Chlor. Portland "A" 2% Gel

PERFORATION RECORD

Acid, Fracture, Shot, Cement Squeeze Record

Shots Per Foot	Specify Footage of Each Interval Perforated	(Amount and Kind of Material Used)	Dept.

TUBING RECORD Size Set At Packer at Liner Run  Yes  No