

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


4-26-3E

Company- BEAUMONT PETRO. CO.
Farm- Chas. Zuercher No. 1

SEC. 4 T. 26 R. 3E
NW NW NW

Total Depth. 3300'
Comm. 7-13-57 Comp. 8-1-57
Shot or Treated.
Contractor. Beaumont Petro. Co.
Issued. 7-4-59

County Butler
KANSAS



CASING:

10 3/4" 108' w/85 sx cem.
7" 2327' w/125 sx cem.

Elevation. 1306' RR

Production. DRY

Figures indicate Bottom of Formations.

R.B. 5' 6 above G.L.	
cellar	5
soil	30
sand, gravel	40
lime, shale	108
lime	680
shale, lime stks	1100
shale	1140
lime, shale brks	1780
shale	1980
lime	2155
shale, lime	2288
lime	2460
shale	2553
lime	2580
lime, shale	2730
lime	3048
shale, lime	3090
lime, shale	3134
lime	3195
shale, lime	3234
lime	3300 RTD.
Cable Tool	
lime	3227 1/2 Effective T.D.
Total Depth	

TOPS:	
Kansas City limestone	2288
B/Kansas City Ls.	2450
Marmaton Ls.	2520
Cherokee Sh.	2674 ?
Mississippi Cht.	2728
Mississippi Dol.	2736
Mississippi Ls.	2776
Kinderhook sh.	3048
Viola Do.	3109
Sikpson SS	3172
Arbuckle Dol.	3234

TOPS: SCOUT	
Conglomerate	2717

DST #1 - 2729-2737