

5-26-3E

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AUGUSTA OIL CO.
Farm- Levering No. 1

SEC. 5 T. 26 R. 3E
SW SW SW

Total Depth. 2847'

Comm. 6-5-57

Shot or Treated.


Contractor.

Issued. 11-30-57

Comp. 7-5-57

County Butler

KANSAS



Elevation. 1314' DE

Production. 25 BOPD

CASING:

8 5/8" 129'
5 1/2" 2846'

Wellers log 0-1600

soil-clay	22
sand-gravel	34
limestone-shale	190
limestone-shale strks	305
limestone-shale	420
red rock	432
limestone-shale	830
red rock	840
shale-shells	1310
limestone-shale strks	1572
limestone	1600
limestone w/shale strks	1608
Electric log	1600-2000
shale	1616
limestone	1630
shale-limestone stks	1670
limestone	1698
shale	1714
limestone	1752
shale-limestone stks	1770
limestone-possibly	
sdv	1790
shale-limestone stks	1830
limestone-possibly sand	1866
shale	1951
limestone	1963
shale	1979
limestone	1993
shale, possibly some	
thin sand strks	2000
Sample log fr 2000 to	
total depth.	
shale-some strks sand	2040
at top	
limestone-few thin	
shale strks	2080
limestone, chalky	2111
shale gry-grn	2113
limestone	2134
limestone-tan to brwn	2176
shale w/limestone strks	2179
limestone brwn	2198
shale-gry-brwn	2209
limestone-gry-brwn	2214
limestone, chalkt	2229
limestone	2231
shale-gry-maroon	2317
limestone gr, brwn	2322
shale	2325
limestone as above	2336
shale	2344
limestone	2370
shale w/thin limestone	
strks	2374
shale, gry-grn	2410

Figures indicate Bottom of Formations.

limestone, tan to brwn-	
some thin shale strks	2414
limestone	2420
limestone as above,	
some chert	2426
shale	2430
limestone tan to brwn	2468
limestone	2480
shale, gr, grn-gry	2499
limestone	2501
shale as above	2536
shale as above, some	
thin limestone strks	2544
shale as above	2549
limestone, gry-tan to	
brwn-shaly; tr chert	2561
shale as above	2564
limestone as above	2567
shale as above	2571
sand, grn-gry, shaly,	2580
shale as above	2594
limestone	2601
shale as above	2607
limestone, brwn; some	
grn-gry limestone	2610
shale, as above	2627
limestone	2634
shale as above, some	
thin limestone strks	2648
limestone	2652
shale, gry, grn, brwn	2665
limestone, tan, brwn, gry.	
Some chert. Some shale	
strks	2683
shale as above, strks	
limestone as above	2722
limestone, gr-brwn;	
some strks shale as above	2736
shale as above	2754
chert, gr-gry, brwn	2759
shale, grn-gry, tr chert	
as above	2780
limestone, shaly, some	
chert	2783
chert. Some gry & grn	
cheet	2792
shale, grn-gry	2794
Dolomite	2804
Dolomite as above. Prob-	
able tr maroon shale.	
Possible tr chert	2815
limestone; some lime-	
stone grn-brwn. Tr glauconite	2824
chert	2829
chert as above w/purple	
maroon shale	2834

chert 2847
Still in Mississippi
Zone #4 2847
Total Depth
TOPS:
Lansing 2040
B/Lansing 2229
Kansas City Lime-
stone 2317
B/Kansas City 2475
Mississippi 2780
Tr free oil 2783-2792
DST #1--2782-89 Mississ-
ippi-Zone #1 - open 1 hr.
good blow throughout test.
Rec. 500' gas, 375' oil.
60' HOCM. 315' wtr -
slightly Oil cut at top.
IEHP - failed to get.
IFP 30 p.s.i. FFp 330
p.s.i. FBHP 750 p.s.i.
15 min.
Ran Schlumberger.
Completion Data:
6-25-57- Ran Lane-Wells
Gamma Ray Collar locator
log - measurements check-
ed with Schlumberger log.
Perforated 6 holes 2825-
27. Hole filled up with
615' of salt wtr. in 15
mins. 1500' salt wtr in
1 1/2 Hrs.
Set Lane -Wells plug 2814
(top of plug).
Perforated 6 holes 2783-85.
60' oil & 48' wtr in 20
mins.
Started swabbing well.


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AUGUSTA OIL CO.
Farm- Levering No. 1

SEC. 5 T. 26 R. 3E
SW SW SW

Total Depth. 2847'
Comm. 6-6-57 Comp. 6-30-57
Shot or Treated.
Contractor.
Issued. 8-10-57

County Butler
KANSAS



CASING:
8" 125'
5" 2847'

Elevation. 1316 RB

Production. 25 BOPD

Figures indicate Bottom of Formations.

soil-clay	22
sand-gravel	34
lime-shale	190
lime-shale strks	305
lime-shale	420
red rock	432
lime-shale	830
red rock	840
shale-shells	1120
shale-shells	1310
lime-shale strks	1572
lime	1725
shale	1735
lime-shale	2108
lime	2215
shale-shells	2317
lime-Kansas City	2400
lime	2480
shale	2638
shale-Conglomerate	2783
Mississippi chat	2847
Total Depth	

TOPS: Scout	
Kansas City	2320
Mississippi	2780