


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- K T WEIDEMAN
Farm- Ethel M. Wait No. 1

SEC. 5 T. 26 R. 3E
SE SE SE

Total Depth. 2767½
Comm. 4-6-50 Comp. 4-26-50
Shot or Treated.
Contractor.
Issued. 11-3-51

County Butler
KANSAS



Elevation. 1315

Production. 8 bbls.

CASING:

8 5/8" 80' cem w/60 sxs.
5½" OD 2749' cem w/45 sxs.

Figures Indicate Bottom of Formations.

surface hole	80
shale, lime, strks	240
lime, shale, brks	460
shale, shells	700
lime	740
shale, lime strks	800
lime, shale brks	835
shale, shells	993
lime	1030
shale, shells	1060
lime	1087
shale, lime	1125
lime	1180
shale	1234
lime, shale, brks	1290
shale	1437
lime	1610
lime, shale	1640
lime	1725
shale, shells	1740
sandy shale	1753
lime	1772
lime, shale	1790
shale	1927
lime	2005
lime, shale brks	2110
lime	2155
shale, shells	2195
shale, lime	2275
shale	2289
lime	2454
shale	2505
shale, shells	2725
ch. conglomerate	2736
conglomerate shale	2745
ch. conglomerate	2753
Mississippi chat	2755 RTD
Cable tools	
Mississippi chat	2767½
Total depth	

Tops:

Kansas City Lst.	2289
Base Kansas City Lst.	2454
Mississippi ch.	2753

Rotary Table to Ground
Level 3'6".