

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas


7-26-3E

Company - JOHN P. GATY  
Farm - De Moss No. 1

SEC. 7 T. 26 R. 3E  
NW SW SW

Total Depth. 2866  
Comm. 12-3-48 Comp. 2-17-49  
Shot or Treated.  
Contractor. Earl Wentworth  
Issued. 5-14-49

County. Butler  
KANSAS



CASING:  
15 1/2" 110' 10" 1416'  
13 3/8" 1062' 8 1/2" 2177'  
6 5/8" 2625'

Elevation. \_\_\_\_\_  
Init. \_\_\_\_\_  
Production. Pot. 3000 bbls.

		Figures Indicate Bottom of Formations.			
clay	27	shale	1120	shale	2235
gravel	30	lime	1135	lime	2240
shale blk	45	shale	1140	shale	2245
lime	65	lime	1145	lime	2260
shale	100	shale	1150	shale	2275
lime	105	lime	1158	lime	2295
shale	110	shale	1165	shale	2368
lime	125	lime	1175	lime	2470
shale	180	shale	1185	shale	2475
lime	185	lime	1205	lime	2480
shale	200	shale	1210	shale blk	2483
lime	215	lime	1220	lime	2500
shale	220	shale	1270	shale	2505
lime	270	lime	1275	lime	2530
shale	280	sand	1300	shale	2600
lime	370	shale	1320	lime	2607
shale	375	lime	1365	shale	2640
lime	420	lime	1372	lime	2645
shale	425	shale	1380	shale	2675
red rock	430	shale blue	1382	lime	2680
lime sdy	445	lime	1390	shale	2690
shale	460	shale	1435	lime	2700
lime	475	lime	1485	shale	2719
red rock	480	shale	1520	lime	2733
lime	530	lime	1545	shale	2740
shale	550	shale	1555	lime	2770
lime	565	lime	1560	shale	2805
shale	570	shale	1565	lime	2808
lime	580	lime	1570	V C. shale	2815
shale	585	shale	1575	chert	2824
shale blue	590	lime	1585	dolomite	2828
lime	600	shale	1605	chert	2835
shale blue	610	lime	1620	dolomite	2851
lime	620	shale	1630	lime	2856
shale wht	625	lime	1645	chert	2866
shale	640	shale	1660	Total depth	
lime	650	lime	1665		
shale, shells	700	lime	1670	Tops:	
lime	710	shale	1675	Kansas City Limestone	2368
shale	720	lime	1705	Mississippian Limestone	
lime	727	shale	1715		2815
shale, shells	765	lime	1755		
shale	775	shale	1760	WATER RECORD:	
lime	805	lime	1800	HPW 1050-60	
shale	820	shale	1820	HPW 1275	
lime	825	lime	1840	1/2 BWPH 1520-25	
shale	850	shale	1880	HPW 2165	
lime	855	shale sdy	1930	Wtr 2430-35'	
shale	880	shale	2005	Show of free oil 2819-24	
red rock	890	lime	2035	Free oil 2863	
shale	910	sand hrd	2045	HFO 2866'	
red rock	915	lime	2055		
lime	920	shale sdy	2090		
red rock	925	shale	2135		
lime	945	lime	2177		
shale	1050	shale	2180		
sand	1060	lime	2215		
shale	1064	shale	2220		
sand	1075	lime	2230		