

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY

508 East Murdock Wichita, Kansas

8-26-3E


Company - K. T. WIEDEMANN
 Farm - Breneman No. 1

SEC. 8 T. 26 R. 3E
 NW NW NW

Total Depth. 2864
 Comm. 5-24-49 Comp. 7-2-49
 Shot or Treated.
 Contractor.
 Issued. 6-3-50

County. Butler

KANSAS



CASING:

8 5/8" 80
 5 1/2" 2797 cem' w/25 sx.

Elevation. 1329 *Ind*

Production. Dry

Figures Indicate Bottom of Formations.

Rotary Table to Ground Level

shale & shells 240
 lime, shale breaks 660
 shale & shells 690
 shale 1285
 lime 1335
 shale & shells 1375
 shale, lime streaks 1459
 shale & shells 1490
 lime & shale 1510
 shale 1560
 lime 1670
 lime, shale breaks 1800
 shale 1865
 shale, lime streaks 1970
 shale & lime 1992
 shale 2050
 lime, shale breaks 2165
 lime 2215
 lime & shale 2230
 shale & shells 2285
 lime & shale 2355
 lime 2525
 shale & lime 2640
 shale, lime & shells 2715
 shale & lime 2780
 shale 2797
 lime cherty, Miss. 2800
 Rotary Total depth
 Cable Tools

Drilling-In Data

6-24-49

chat - 20 minutes 2800-02
 1st Free Oil here
 One Hour Test - 1st bailer
 full of oil.

2nd bailer 3/4 full of oil.
 Seems 50 to 60' fillup 1 hr.

Two Hour Test = 270' Fillup
 1 1/2 bailers very salty water.
 Test about 1 BW per hr - Salty
 chat - 10 minutes 2802-03

Fluid level 310'

6 bailers salty water - 7th
 bailer mostly oil.

6-25-49

8 a.m. - 1300' fluid in Hole
 After 35 bailers water, fluid
 level 930'

6-26-49

8 a.m. fluid level 1477'

6-30-49
 Pumping test 1/4 Oil 3/4 water
 7-1-49
 Fluid level 890'
 white chat - 8 minutes 2803-04
 milky chat - 15 " 2804-05
 stains seems more oil.
 chat - 14 min. 2805-06
 florescence
 chat - 14 min. 2806-07
 chat - 11 min. 2807-08.
 More florescence
 chat - 10 min, more
 florescence 2808-09
 chat - 14 min 2809-10
 coarse chat - 16 min 2810-11
 7-2-49
 Fluid level 950'
 dolomite - 21 min 2811-12
 dolomite - 11 min. 2812-13
 dolomite - 11 min. 2813-14
 dolomite - 8 mins. 2814-15
 dolomite - 15 min. 2815-16
 7-3-49
 shot 10 qts 2802-09
 More water
 7-5-49
 We tried to cement off water.
 12-3-49
 Drilled out cement - failed - HFW
 lime 2864
 Total depth

Abandoned & plugged.
 HFW 2802-9

Tops:

KC Lime 2330
 Base KC lime 2495
 Miss. Chat 2797