

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


9-26-3E

Company- LEE H. CORNELL, ETAL
Farm- Benfer No. 1

SEC. 9 T. 26 R. 3E
SW NW SW

Total Depth. 2810'
Comm. 2-7-63 Comp. 2-14-63
Shot or Treated.
Contractor. SeRoBee Drilg. Co., Inc.
Issued. 4-13-63

County Butler
KANSAS



Elevation. 1355' KB

Production. 4 1/2 BOPH, NW

CASING:

8 5/8" 167' cem w/150 sx.
4 1/2" 2798' cem w/75 sx.

Figures indicate Bottom of Formations.

top soil & clay	35
lime	167
lime & shale	775
shale & shells	935
lime & shale	2333
Kansas City	2496
lime & shale	2723
Cherokee	2770
Conglomerate	2796
Mississippian chert	2810
Total Depth	

TOPS:

Kansas City	2333
Base Kansas City	2496
Cherokee	2723
Conglomerate	2770
Mississippian	2796

DST 2798-2810' Op 1 hr. Strong blow.
Rec. 1028' gassy oil, no water. ICIP 584#,
IFP 202#, FFP 420#, FCIP 631#.