


Location SE corner.

Sec. 9 T. 26 R. 6E.

Casing Record

County- Butler.

10" 1867 Farm- Campbell No. 1  
 20" 8 1/2" 2387 Company- Arkansas Fuel Oil Co.  
 15 1/2" 170 65/8" Contr.-  
 12 3/8" 1251 53/16" 2756 Comm.- 7/12/1929. Comp.- 9/11/1929.  
 Total Depth 2771 Shot Quarts Between  
 Correspondence Regarding This Well Should Be Referred to



Elevation

Figures Indicate Bottom of Formations.

Initial Production 35 bbls.

Date Issued. 9/28/1929.

Formation	Depth	Formation	Depth	Formation	Depth
sand	15	3 BW at 1455'		Oil 2762-64	
shale	40	lime	1470		
sand water	45	shale	1485	TD.	2771
shale	87	lime & shale	1500		
lime	92	lime	1535		
shale	99	shale	1540		
lime	123	lime	1570		
shale	138	shale	1575		
red rock	150	lime	1585		
lime	300	shale	1595		
1/2 BW at 275'		lime	1610		
shale	315	shale	1615		
red rock	320	lime	1620		
lime & shale	350	shale	1645		
red rock	355	lime	1675		
lime	370	shale	1690		
shale	375	lime	1735		
lime	400	shale	1750		
red rock	410	lime	1765		
lime	430	shale	1780		
shale	440	lime	1795		
shale & shells	475	shale	1815		
lime	485	shy lime	1830		
shale	535	4 BW at 1830			
lime	545	shale	1930		
shale	555	lime	1940		
red rock	560	shale	1975		
lime	595	lime	1985		
lime & shale	645	shale	2030		
1/2 BW at 645		lime	2075		
lime	675	sand	2080		
shale & shells	700	lime	2180		
lime	730	sand	2195		
shale	805	lime	2230		
red rock	810	shale	2240		
shale & shell	830	shale & shells	2255		
brown shale	850	shale	2325		
lime & shale	900	lime	2335		
shy lime	905	shale	2340		
shale	935	lime	2360		
3 BW at 900'		lime	2423		
lime & shale	960	shale	2427		
shale	1010	lime	2440		
sand	1055	sand	2448		
HFW 1010'		HFW 2445'			
shale	1125	lime	2450		
lime	1130	shale	2455		
shale	1180	lime	2480		
sand water	1225	brown shale	2500		
lime	1257	shale	2550		
shale	1261	lime	2565		
lime	1275	8" U. R. to 2550'			
shale	1290	shale	2585		
lime	1295	lime	2605		
shale	1305	shale	2625		
lime	1315	lime	2680		
shale	1333	shale	2685		
lime	1340	lime	2700		
shale	1380	shale & shells	2725		
lime	1415	black shale	2734		
shale	1445	shale pink & brown	2738		
lime	1455	lime	2741		
sand	1459	red rock & green shale			
3 BW at 1455'			2756		
		chat	2771		