


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- REX & MORRIS ET AL
 Farm- Straw No. 1

SEC. 9 T. 26 R. 3E
 NW NE SE

Total Depth. 2775' PB 2760'
 Comm. 8-13-56 Comp. 9-26-56
 Shot or Treated.
 Contractor. Rex & Morris Drlg. Co.
 Issued. 10-27-56

County Butler
 KANSAS



Elevation. 1335' DF

Production. Dry

CASING:

8 5/8" 104' w/160 sx cem.
 5 1/2" 2753' w/50 sx cem. P 2360'

Figures indicate Bottom of Formations.

shale	25
lime sdy-HFW	35
shale	45
lime	50
shale	70
lime	75
shale	85
lime	100
shale	106
lime-shale	2025
lime	2165
shale-lime	2306
lime	2478
lime-shale	2753
chat	2767
lime	RTD 2775 RB
H.U.S.T. & D.P. & C.P.	RTD 2772 DF
Total Depth PB	2760'

TOPS: Scout

Kansas City	2322
B/Kansas City	2476
Mississippi chat	2753
Mississippi sand	2767

Test 465' fluid in 16 hrs. (28 gal. wtr.)
 Test 88 BOPH. Test 425' fluid (10 gal. wtr. & 9 1/2 BO) in 16 hrs.
 Acid Petro-Frac w/5000 gals. & 5000# sand.
 Used 189 B . load oil. Swab down rec. 80 BW & 84 BO.
 Final test, 42 BWPH w/small amount of oil
 Test approx. 18 BWPH w/trace oil.