

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location Southwest Corner.

Sec. 10 T26 R3E.

Casing Record.

County. Butler.

JUN 22 1929

10" Farm. Glancey No. 1
 20" 8 1/2" Company. Lario Oil and Gas Company.
 15 1/2" 65/8" Contr.
 12 1/2" 53/16" Comm. 4-12-29 Comp. 6-14-29
 Total Depth. 2765 Shot Quarts Between.
 Correspondence Regarding This Well Should Be Referred To.



Elevation. 1359

Figures Indicate bottom of Formations.

Initial Production Est 400 bbls.

Date Issued. 6-22-29

Formation	Depth	Formation	Depth	Formation	Depth.
lime wh hard	15	shale gr soft	1020	lime grey hard	1985
shale blk soft	20	HFW 1020		sdv shale gr soft	2009
shale gr soft	40	sand soft	1038	shale dark soft	2025
HFW 40		sand grey soft	1060	lime gr hard	2080
lime grey soft	45	slate blue soft	1070	LBW 2070	
shale blue soft	100	sdv shale grey	1085	lime gr med	2095
15 1/2 at 100		shale gr soft	1098	HFW 2085	
lime hard	105	shale blue soft	1130	lime gr hard	2135
shale soft	110	lime grey hard	1140	lime gr hard	2140
lime hard	115	shale blue soft	1150	shale dark soft	2160
lime white hard	120	lime white hard	1155	lime grey hard	2190
shale blk soft	125	shale	1180	lime white hard	2225
lime wh hard	135	12 1/2 casing	1150	shale blue soft	2230
shale blk soft	150	shale blue soft	1200	lime wh hard	2235
shale green soft	155	HFW 1200		shale grey soft	2310
red rock soft	165	water sand gr sft	1240	lime gr hard	2350
lime gr hard	315	water sand gr soft	1246	shale bluesoft	2352
shale blue soft	335	lime wh hard	1275	lime grey hard	2355
lime gr hard	340	lime dk hard	1315	lime grey hard	2370
shale blue soft	360	shale blk soft	1324	lime grey soft	2379
red rock soft	370	lime gr hard	1326	HFW 2375	
lime grey hard	415	shale blk soft	1385	lime grey hard	2416
red rock soft	425	lime gr hard	1390	8 1/2 casing	2390
lime white hard	440	lime wh hard	1435	shale blue soft	2418
shale blue soft	445	shale blue soft	1445	lime grey hard	2422
lime grey hard	450	sdv lime med	1455	lime white hard	2440
shale blue soft	460	4BW 1450		shale blue soft	2455
lime grey hard	465	lime hard	1464	lime grey hard	2475
shale blue sot	475	lime white hard	1480	shale blue sft	2535
lime hard	495	shale blk soft	1503	sdv lime & blue	
shale blue soft	500	lime grey hard	1507	shale	2560
shale grey	510	lime	1510	shale white soft	2581
lime grey hard	535	shale blue soft	1515	lime wh hard	2590
shale blue soft	555	lime white hard	1557	shale dark soft	2620
lime grey hard	565	shale blue soft	1563	lime gr hard	2645
shale blue soft	575	lime grey hard	1580	shale blue soft	2650
lime grey hard	585	shale blue soft	1593	lime grey hard	2675
shale grey soft	605	lime grey hard	1600	shale blue soft	2688
lime grey hard	610	shale blue soft	1613	lime grey hard	2690
shale blue soft	620	lime grey hard	1627	shale & shells blue	2718
lime hard	625	shale dark soft	1633	lime grey hard	2730
shale and shale		lime dark hard	1638	red rock soft	2735
shells	665	shale blk soft	1654	red rock and green	
lime white hard	690	lime grey hard	1690	shale	2738
LBW 675		shale dark soft	1705	lime sdv white	2741
shale bluesoft	700	lime grey hard	1745	running 605/8 casing.,	
shale soft	705	slate blue soft	1751	lime sdv grey	2758
lime hard	710	shale and shells	1760	sdv lime hard	2760
shale soft	725	lime brokn med	1770	chat	2765
lime hard	730	lime gr hard	1780	Oil found in chat form-	
lime grey hard	740	shale blue soft	1790	ation between 2760-and	
shale blue soft	775	lime grey hard	1803	2765 Total Depth.	
lime grey hard	785	shale blue soft	1825		
shale blue soft	810	sand grey med	1850		
red rock	820	7BW 1850			
shale blue soft	840	sdv shale light			
red rock soft	845	soft	1870		
shale blue soft	865	shale blue soft	1880		
lime grey hard	870	sdv shale gr sft	1885		
shale blue soft	890	HFW 1885			
sdv lime grey	900	shale grey soft	1939		
2 BW 890		Running 10" casing			
shale grey soft	935	at 1885.			
lime grey hard	940	lime white hard	1945		
		shale blue sft	1975		