

20-26-3E

10" 1772
20" 8 1-4 2498
15 1-2 32 6 5-8 2666
12 1-2 1070 5 3-16

FARM Marnane NO. 1 COUNTY
COMPANY Phillips Petroleum Co.
CONTRACTOR
COMMENCED 2-24-27. COMPLETED 4-4-27.



TOTAL DEPTH 2904'. SHOT QUARTS BETWEEN
CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Phillips Petroleum Co.

ELEVATION 137' JUN 18 1927
INITIAL PRODUCTION Dry.

Bartlesville, Okla.
FIGURES INDICATE BOTTOM OF FORMATIONS.
REMARKS 6/18/27.

Formation	Depth	Formation	Depth	Formation	Depth
soil dark sft	10	shale blue sft	985	shale white sft	1860
shale dark sft	75	shale gray sft	1000	shale dark sft	1870
lime white hrd	80	lime gray hrd 2 BW	1010	lime white hrd	1875
sand white sft	85	shale blue sft	1040	shale white sft	1950
(15 1/2" at 83')		shale blue sft	1045	lime white hrd	1955
shale white sft	100	sandy shale brown sft	1065	shale white sft	2000
lime white hrd	120	sand brown sft	1070	lime white hrd	2020
shale black sft	135	(12 1/2" 1070')		shale white sft	2045
shale blue sft	160	lime white hrd	1075	lime white hrd	2055
shale gray sft	180	shale brown sft	1115	lime white hrd	2160
lime white hrd	190	lime white hrd	1135	2 BW PH 2125'	
shale gray sft	215	shale blue sft	1145	lime white hrd	2165
red rock red sft	230	lime white hrd	1175	(12 BW 2165-2175')	
lime white hrd	260	lime white hrd	1185	lime white hrd	2175
lime white hrd	270	shale blue sft	1195	sandy lime blue sft	
shale blue sft	280	lime white hrd	1205		2200
lime white hrd	300	shale dark sft	1230	8 hrs repairing reel	
shale black sft	310	lime white hrd	1240	lime white hrd	2245
lime white hrd	350	shale white sft	1255	lime white hrd	2270
lime white hrd	380	lime white hrd HFW	1250	shale gray sft	2330
shale gray sft	395	sand white sft	1325	shale gray sft	2380
lime white hrd	425	(10" 1325')		lime white hrd	2385
lime white hrd	440	shale white sft	1330	shale white & sft	2395
lime white hrd	430	lime white hrd	1340	lime white sft	2405
shale gray sft	485	shale blue sft	1350	lime white hrd	2430
red rock red sft	490	lime white hrd	1365	(8 1/4" 2392' SL)	
lime white hrd	500	shale drk sft	1375	lime white hrd HFW	2455
shale gray sft	515	lime white hrd	1385	lime white hrd	2490
lime white hrd	525	shale dark sft	1400	(UR 8 1/4" 2392-2490')	
shale blue sft	535	shale blue sft	1430	(6 5/8" 2665')	
shale blue sft	540	shale blue sft	1450	lime white hrd	2535
lime white hrd	575	lime white hrd	1460	lime white hrd	2550
shale gray sft	590	shale blue sft	1480	shale blue sft	2620
lime white hrd	600	lime white hrd	1500	shale blue sft	2665
shale dark sft	625	shale blue sft	1510	Caving	
lime white hrd	645	lime white hrd	1530	shale blue sft	2685
shale white sft	655	shale dark sft	1540	lime white hrd	2775
shale blue sft	675	lime white hrd	1550	shale gray sft	2826
lime white hrd	685	shale blue sft	1575	lime white hrd	2860
shale blue sft	695	lime white hrd	1585	lime white hrd	2880
lime white hrd	710	shale gray sft	1625	lime white hrd	2904
shale B. sft	725	slate white sft	1645	Total Depth	2904'
lime white hrd	740	lime white hrd	1690		
lime white hrd	760	lime white hrd HFW	1710		
shale white sft	770	sandy lime gray sft	1720		
lime white hrd	800	lime white hrd	1745		
shale blue sft	820	shale white sft	1770		
lime white hrd	845	(10" 1765')			
shale gray sft	870	shale blue sft Pull csg.			
lime white hrd	380	reaming	1785		
shale blue sft	890	lime white hrd	1805		
red rock red sft	910	shale white sft	1810		
shale blue sft	330	lime white hrd	1815		