

27-26-3E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE OIL COMPANY
Farm- Thacker No. 1

SEC. 27 T. 26 R. 3E
NE NE SW

Total Depth. 3250'
Comm. 3-26-60 Comp. 4-7-60
Shot or Treated.
Contractor. White & Ellis Drilling Co.
Issued. 8-6-60

County Butler
KANSAS



CASING:

10 3/4" @ 313' w/250 sks. cem.

Elevation. 1361' K.B.
(5' above GL)

Production. Dry

Figures Indicate Bottom of Formations.

soil	5	Schlumberger Electric Logs were	
lime & shale	45	run.	
lime	155		
lime & shale	260	No cores were taken.	
lime	275		
lime & shale	355		
lime	545	Drill Stem Test #1	3100-3112
shale & lime	940	(12' anchor)	
lime & shale	1160	#2	3132-3153
shale & shells	1210	(21' anchor)	
shale & lime	1660		
lime	1776		
shale	1855		
sand	1890		
sandy shale	1905		
shale	1972		
lime	2175		
shale & lime strks.	2326		
lime	2494		
lime & shale	2745		
shaley (congl.)	2785		
lime	3057		
shale	3106		
lime	3112		
lime, Viola	3135		
sand, Simpson	3211		
dolomite, Arbuckle	3250	RTD	
Total Depth			

TOPS:

Oread limestone	1659
Heebner shale	1692
Base Heebner shale	1698
Base Oread limestone	1748
Lansing limestone	1971
Base Lansing Limestone	2168
Kansas City Limestone	2324
Base Kansas City limestone	2485
Cherty Conglomerate	2768
Base Cherty conglomerate	2785
Varigated cherty conglomerate	2785
Mississippi limestone	2812
Base Mississippi limestone	3050
Viola dolomite	3104
Base Viola dolomite	3131
Simpson	3131
Base Simpson	3196
Arbuckle dolomite	3196