

**F.W. MORGAN**  
GEOLOGIST

305 S. WASHINGTON  
ELDORADO, KANSAS 67042

Oct. 13, 1987

ELDORADO (316) 321-1463

Crest Petroleum, Inc.  
Box 445  
Andover, Kansas, 67002

Re: No. 1 Stareck  
Sec. 11-26S-3E  
Butler County, Ks.

Gentlemen:

Enclosed is my geological log on the No. 1 Stareck. On the log is all pertinent information on this well. It ran 2 to 3 feet low to the abandoned producer to the northeast on all reliable geological markers down to the Mississippian. The Mississippian top was 9 feet high to that well.

Unfortunately, the chert reservoir that produced in the abandoned well (primary reservoir in the area) was not present. We found a tan, sucrosic dolomite at the top of the Mississippian with no sign of the chert. The second break in the Mississippian was found at 2753 feet consisting of a chert zone. However, the porosity and oil show were very poor. In addition it was ten feet lower than a dry hole to the southeast that tested water from this zone.

In view of the facts stated above we had no choice but to plug this well as dry and abandoned.

Sincerely,

  
F. W. Morgan

