

21-26-5E


KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY MAGNOLIA PETROLEUM COMPANY
FARM M.A. Koogler NO. 86

SEC. 21 T. 26 R. 5E
LOC. SW NW NW

TOTAL DEPTH 2535 K.B. P.B. to 2529
COMM. 11-25-50 COMP. 12-11-50
SHOT OR TREATED
CONTRACTOR Capitt Drilling, Inc.
ISSUED 2-3-51

COUNTY Butler



CASING

10 3/4" 108' cem. w/80 sx
7" 2470' cem. w/75 sx

ELEVATION 1323 D.F.

PRODUCTION 4 bbls. oil per day & trace water

FIGURES INDICATE BOTTOM OF FORMATIONS

cement	10
cavings	50
lime & shale	1495
sand & shale	1580
shale & shells	1590
lime	1660
shale & lime	1680
lime	1885
shale & lime	1900
shale & shells	2000
lime	2215
shale & lime	2235
lime	2265
shale & lime	2470
lime, Viola	2497
sand, Simpson	2528
sandy lime	2529
redrock, green & black shale	2530
shale black	2535
Total depth, K.B.	2535
Plugged back	2529
Tops:	
Viola	2470 K.B.
Simpson	2497 K.B.

Azidized Viola w/500 gals. acid.