

CITIES SERVICE OIL CO.
Price No. 12.

SEC.5 T.26 R. 5 E
NW SW SE
990'N 330'E S $\frac{1}{4}$ Cor.

Total Depth. 2481' PB 2468'
Comm. 8-17-41 Comp. 8-30-41
Shot or Treated.
Contractor. Sharon Drlg.Co., Inc.
Issued. 12-6-41

County. Butler



CASING:
7" 2434' Cem.

Elevation.

Production. 130 BO, 33 BW

Figures Indicate Bottom of Formations.

surface	3
lime	260
lime & shale	435
shale & shells	630
shale & lime	800
lime	840
shale	1065
lime & shale	1240
lime	1260
shale	1355
lime shale	1595
shale	1610
lime	1635
shale	1694
lime	1790
shale	1970
lime	2075
shale	2085
lime	2135
shale & lime	2175
shale & shells	2428
shale	2434
lime	2435
lime?	2445
lime, sh oil	2457
dolomite	2481
Total Depth.	

660' Oil in 9 hrs
Az 1000 Gals.
Pmpd chiefly wtr
P. B. from 2481 to 2468 &
shot w/50 Qts. Nitro.
from 2449 to 2464
filled up 2134' after shot

Top Lansing 1693
lt. sh oil 1713-32
Top Kansas City lime 1970
sh oil 1983-2000
Top Arbuckle 2434
sh oil 2434-81