


BISAGNO BROS.
Bisagno "A" No. 1.

SEC. 35 T. 26 R. 5E.
CNE NE

Total Depth. 2753
Comm. 10-22-40 Comp. 12-1-40
Shot or Treated.
Contractor. Petroleum Drilling Co.
Issued. 10-25-41

County Butler.



CASING.

15 $\frac{1}{2}$ " 63'7"
12 $\frac{3}{4}$ " 1037'
10" 1920'
8 $\frac{1}{4}$ " 2430
reduced 65/8" 2694 corr to 2690

Elevation.

Production. 50 B.

Figures Indicate Bottom of Formations.

cellar	10	shale	725	shale	1685
lime	25	lime	730	shale	1705
broken lime	33	shale	735	lime	1725
lime	45	broken lime	750	lime	1730
lime	80	shale	755	shale	1735
shale	85	shale	795	lime	1750
shale	120	lime	800	shale	1805
lime	125	shale	812	lime	1990
red rock	130	lime	845	shale	1995
shale	140	shale	853	broken lime	2015
lime	150	lime	860	broken lime	2035
shale	155	lime	902	shale	2130
lime	175	shale	965	lime	2190
shale	180	lime sdy	970	shale	2192
red rock	185	shale	980	lime	2210
lime	205	broken sdy lime	990	lime	2290
lime	210	shale	1015	shale	2302
shale	220	shale	1037	lime	2315
broken lime	245	lime	1039	shale	2380
lime	250	broken lime	1048	lime	2382
shale	255	shale	1062	shale	2400
lime	260	lime	1070	sand water	2420
shale	275	lime	1075	sdv shale	2430
lime	282	shale	1155	lime	2440
shale	315	lime	1180	shale	2445
lime	325	shale	1190	shale	2450
shale	335	lime	1220	lime	2455
lime	365	shale	1245	shale	2480
shale	370	lime	1255	lime	2490
lime	380	shale	1265	shale	2525
shale	420	lime	1270	lime	2540
lime	430	shale	1280	shale	2615
shale	450	lime	1295	lime	2620
lime	460	shale	1300	shale	2685
shale	465	lime	1325	sdv shale	2690
lime	470	shale	1330	broken sand	2710
shale	475	lime	1350	sand	2753
lime	495	shale	1355	Total Depth.	
shale	500	lime	1365	1 BWPFR 335-45	
shale	505	shale	1370	1 BWPFR 670	
lime	510	lime	1385	4 BWPFR 735-750	
shale	540	shale	1390	2 BWPFR 980-985	
broken lime	555	lime	1410	1 $\frac{1}{2}$ BWPFR 1470-1475	
shale	560	lime	1415	1 $\frac{1}{2}$ BWPFR 1600-1610	
lime	565	shale	1425	3 BWPFR 1855-65	
shale	580	shale	1435	1 $\frac{1}{2}$ BWPFR 2150	
shale	595	lime	1445	4 BWPFR 2195-2215	
red rock	600	shale	1465	5 BWPFR 2405	
shale	610	lime	1480	cave 2390	
lime	615	lime	1505	5 BWPFR 2405-2420	
shale	620	shale	1510	Scum oil 2705-2710	
red rock	625	lime	1515	small show oil 2710-14	
shale	630	shale	1530	steel line run 2714 corr from	
shale	640	lime	1545	2718	
lime	645	shale	1600	show oil 2728-2733	
shale	660	lime	1605	Good sh free oil 2733-40	
lime	675	broken lime	1625	inc in oil 2740-2745	
shale	685	broken lime	1640	shot with 80 qts.	