

CASING RECORD

LOCATION SE of NW of SE

SEC 27 T26 R 7E

PLOTTER

27-26-7E Jameson

20" 10" 1658 FARM E. Willhite NO. 1 COUNTY Butler
 15 1-2 8 1-4 2128 COMPANY Brenan Wixen and Sheldon
 12 1-2 950 5 3-8 CONTRACTOR

12 1-2 950 5 3-16 COMMENCED Sept 30, 1925 COMPLETED Oct 25, 1925.

TOTAL DEPTH 2163 $\frac{1}{2}$ SHOT QUARTS BETWEEN

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Brenan Wixen and Sheldon, Eldorado, Kansas.,

FIGURES INDICATE BOTTOM OF FORMATIONS.

(CORRECTED COPY)

INITIAL PRODUCTION Est 75 Bbls.

REMARKS



7
 P. 100
 NE, NW
 C.L.

Formation	Depth	Formation	Depth.
lime and slate	20	lime	1000
lime	30	slate	1050
slate	45	lime	1135
lime	65	slate black	1145
red rock	70	lime	1165
lime	80	slate	1170
slate	95	lime	1185
lime	100	slate	1190
slate	120	lime	1195
lime	130	slate	1200
red rock	140	lime	1235 1BW 1220
lime	160	slate	1260
slate	180	lime	1320
lime	215	slate cave	1330
slate	225	lime	1335
lime	235	slate	1385
slate	240	2 B W	1333
lime	300	slate	1400
slate	310	lime	1440
lime	330	slate	1445
slate	335	lime	1470
lime	340	shale	1490
slate	350	lime	1495
lime and shale	385	slate	1620
lime	390	lime	1630
slate	410	slate	1660
lime	435	set 1658 10" Casing	
slate	465	lime	1662
red rock	470	slate	1725
slate	490	lime	1740
lime	495	sandy lime	1745
slate	590	GOOD SHOW OF OIL 1740-1745	
lime	595	lime	1825
slate	650	sandy lime	1835
lime	655	1 B.W. 1830	
slate	660	lime	1845
lime	665	sandy lime	1870
slate	675	4 BW 1870	
slate	695	lime	1895
lime	705	shale	1975
slate	750	slate	2045
lime	785	lime	2115
slate	790	4 B. W. 2115-2130	
lime	815	lime soft	2130
lime 2 BW 830	835	set 2128 8" Casing	
slate	840	lime	2148
lime	860	shale	2154
slate	865	sandy lime	2163
lime 1 BW 895	895	GOOD SHOW OF OIL 2154	
slate	905	Hole filled up 1200 in first 16 hours	
lime	915	2163 $\frac{1}{2}$ T.D. Well put on Pump 8:00	
slate	945	10/26/25 Pumped 105 bbls in 16 hours.	
lime	950		
set 950 12" casing			
slate	965		