

27 26-7E


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - THE EL DORADO REFINING COMPANY
Farm - Young "B" No. 3

SEC. 27 T. 26 R. 7E
SWc NE

Total Depth. 2742'
Comm. 10-10-45 Comp. 11-11-45
Shot or Treated. Shot w/20 qts. & acid. w/2000 gals.
Contractor. Rex & Morris Drilling Co.
Issued. 3-29-47

County. Butler
KANSAS



CASING:
12 1/2" 886' P 8 1/4" 2135' P Cem. w/25 sx
10 " 1608' P 7 " OD 2709' LI Cem. w/25 sx

Elevation. 1473 ft

Production. 40 bbls.

Figures Indicate Bottom of Formations.

rocks & shale	60	shale	1265	Tested 2 hrs. 1 BO 1/3 BW
shale drk	75	lime	1275	lime dolomitic hrd 2726 1/2
lime lt	90	shale	1280	No increase in oil from
shale drk	100	lime	1310	2714-2725'.
red rock	110	shale	1315	Tested 2 1/2 hrs. 1 BO &
shale lt	120	lime	1325	1 BW.
shale	200	shale	1380	lime dolomitic brwn 2737 1/2
lime	205	lime	1420	Good Saturation
shale	220	shale	1425	Best Pay 2732-37 1/2'
lime & shale	250	lime	1435	lime dolomitic brwn 2742
shale	275	shale	1440	Oil stain-fair sat.
lime	285	lime	1458	Tested 3 hrs. 1 BW & BO
shale	345	shale 1 BWP	1470	Total Depth 2742
lime	360	sand	1485	
1/2 BWP 345-55'		shale sdy	1495	
shale	380	shale	1600	
lime	385	lime	1610	
shale	395	shale	1630	
lime	405	lime	1640	
shale & lime	430	shale	1720	
shale	450	lime	1875	
red rock	455	SSO 1730-40'		
shale	510	1 1/4 BWP 1795-1800'		
red rock	520	1/4 BWP 1835-40'		
shale	530	shale	2025	
lime	540	lime	2130	
red rock	545	1 1/4 BWP 2055-60'		
shale	555	shale	2133	
red rock	560	lime	2173	
shale	565	Small S.O. 2160-66'		
lime	570	shale	2175	
shale	750	lime	2185	
lime	765	shale	2200	
shale	795	lime sdy	2240	
lime	815	3 BWP 2200-10'		
1/2 BWP 800-810'		lime	2255	
shale	825	shale	2280	
lime	830	lime	2290	
shale	860	shale	2325	
shale sdy	875	Cave at 2300'		
shale	940	lime	2335	
lime	955	shale	2390	
shale	965	lime	2405	
shale & lime	985	shale	2420	
shale	1000	lime	2435	
lime	1025	shale	2525	
shale	1050	lime	2535	
lime	1080	shale	2612	
shale	1095	red rock	2618	
lime & shale	1125	shale	2697	
shale	1150	lime	2700	
lime	1215	shale	2709	
1 BWP 1195-1200'		1st S.O. 2709'		
shale	1230	dolomitic lime brwn	2714	
lime	1240	Good S.O. 2709-14'		
shale	1250	shale	2717	
lime	1260	lime dolomitic	2721	
		Some Oil Stain		