


9-26-8E

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- FRANCO-CENTRAL OIL COMPANY
Farm- Hughes No. 0-2

SEC. 9 T26 R. 8E
NE NE SE

County Butler
KANSAS



Elevation. 1431 R.B.

Production. Est. 20 bbls

Total Depth. 2538
Comm. 2-28-52 Comp. 3-31-52
Shot or Treated.
Contractor. White & Ellis Drilling Co.
Issued. 4-26-52

CASING:

8 1/4" 98' cem w/65 sx
5 1/2" 2477' cem w/50 sx

Figures indicate Bottom of Formations.

soil, clay	0-	10
lime		30
red rock		45
lime		60
lime, shale		98
lime		225
shale, lime		554
lime		610
shale, lime		763
shale, shells		845
lime		905
shale, lime		1140
lime, broken		1250
shale		1270
shale, lime		1600
sand		1625
shale, shells		1829
lime		1935
lime, shale		2020
lime, broken		2080
shale, lime		2410
sand		2419
shale, shells		2476
sand		2538
Total Depth		

Tops:

Lansing	1520
Kansas city	1828
Base Kansas City	2054
Top Prue Sand	2295
Base Prue "	2306
(No Upper Bartlesville Sand)	
Top Lower Bartlesville Sand	2476
Base Lower Bartlesville Sand	2520