

19-26-8E

KANSAS DRILLERS LOG
State Geological Survey

WICHITA, BRANCH
API No. 15 — 015 — 20,743
County Number

S. 19 T. 26 R. 8 E
Loc. C W2 of Lot #12
County Butler

Operator
W. N. Bartlett

Address
300 Kaufman Building Wichita, Kansas 67202


Well No. #1 Lease Name Overstreet

Footage Location 1905 feet from (N) line 9000 feet from (E) line
NOTE: This is an Irregular Section

Principal Contractor Berentz Drilling Co. Geologist Clark A. Roach

Spud Date September 22, 1975 Total Depth 2800' P.B.T.D.

Date Completed September 29, 1975 Oil Purchaser



Locate well correctly
Elev.: Gr. 1542
DF 1544 KB 1546

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
		8-5/8"		200'		130	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB
---------------------------------	-----------	---------	-------------	--------------------

Disposition of gas (vented, used on lease or sold) Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

W. N. Bartlett

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Dry Hole

Well No.

1

Lease Name

Overstreet

S 19 T 26S R 8E^E_W (This is an Irregular Section)

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil		2	XXXXXX	KKXX
Shale & Lime		25	Heebner	1458 + 88
Lime w/Shale streaks		265	Toronto	1476 + 70
Shale w/Lime streaks		1045	Douglas	1500 + 46
Shale		1090	Douglas Sand	1596 - 50
Lime w/Shale streaks		1432	Lansing	1769 - 223
Shale & Lime		1769	Kansas City	2074 - 528
Lime		1920	Base K.C.	2238 - 692
Shale & Lime		2074	Marmaton	
Lime (KC)		2238	(Lenapah)	2288 - 742
Shale & Lime		2505	Altamont	2343 - 797
Shale Cherokee		2763	Pawnee	2374 - 828
Lime (Miss.)		2800 RTD	Fort Scott	2446 - 900
			Cherokee	2505 - 959
			Bartlesville zone	2688 - 1142
			Mississippian	2763 - 1217
			Total Depth	2800 - 1254

DST #1 2079' to 2089'. Open 30 min., weak increasing to fair blow.
 Shut in 30 min. Open 60 min., weak increasing
 to a fair blow. Shut in 60 min.
 Recovered 170' of muddy salt water, 1 foot of clean oil.
 ISIP 543 psi; FSIP 543 psi; IFP 10-52 psi. FFP 62-83 psi.

NOTE: No electric log run.

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



W. N. BARTLETT

By

Signature

Secretary

Title

November 12, 1975

Date

18-9P-8E

95345

2482P

15-015-20743

State Geological Survey
WICHITA, BRANCH

19-26-88

LOG OF WELL

OPERATOR Mr. Wm. N. Bartlett

Contractor Berentz Drilling Co.

Overstreet #1
C W/2 of Lot 12
Section 19, Twp. 26s
Rge. 8e
Butler County, Kansas

Commenced w/Rotary 9-22-75
Completed w/Rotary 9-29-75

Casing: 8 5/8" 200' cemented w/130 sacks

Soil	2
Shale & Lime	25
Lime w/Shale strks	265
Shale w/Lime strks	1045
Shale	1090
Lime w/Shale strks	1432
Shale & Lime	1769
Lime	1920
Shale & Lime	2074
Lime (KC)	2238
Shale & Lime	2505
Shale Cherokee	2763
Lime (Miss.)	2800 RTD

RECEIVED
STATE CORPORATION COMMISSION

OCT 2 1975

CONSERVATION DIVISION
Wichita, Kansas