

Company- KEWANEE OIL CO.  
Farm- Wichita Unit: "E" No. 47

SEC. 3 T. 27 R. 1E

NW SW SW

Surf: 1290' FSL & 71' FEL, SE $\frac{1}{4}$  Sec.

Btm. Hole: 246.26' FWL &amp; 1220.20' F

County Sedgwick

KANSAS

SW $\frac{1}{4}$  Sec.

Total Depth. 3362'


Comm. 6-25-58

Comp. 6-14-58

Shot or Treated.

Contractor. Peak Drlg. &amp; Adair Drlg. Co.

Issued. 9-20-58



## CASING:

9 5/8" 304.23' CM w/325 sx cem.

5 1/2" 3361' CM w/100 sx cem.

Elevation. 1313

Production. Nat. Swbd. 249.30 BO  
& 228.20 BW 4 2/3 hrs.

Figures indicate Bottom of Formations.

sand, shale	128
sand	160
lime	290
sdv lime	314
sand, lime stks	560
shale, lime sdv	760
sand, shale	1170
sand, shale, lime stks	1500
shale, sand	1580
lime	1625
lime, shale	1667
sand, lime	1777
shale, lime	1842
lime	1905
lime, shale	1924
lime, shale sdv	2115
shale, lime	2145
shale	2241
shale, lime stks	2270
shale	2446
shale, lime stks	2485
lime	2636
lime, sand	2715
lime, shale	3015
lime	3068
lime, chert	3089
lime	3206
lime, shale	3323
sdv shale	3362
Total Depth	

TOPS:	Meas. T. Vert.
Kansas City	2522 2503
Burgess Sand	3007 2980
Mississippi	3011 2984
Viola	3360 3326

Completion: Viola, open hole,  
natural. 3361-62' Measured  
depth.