

126495

SIDE TWO

ACO-1 WELL HISTORY

OPERATOR Osage Drilling, Inc.LEASE Mills "C"SEC. 1 TWP. 27 RGE. 12E

FILL IN WELL INFORMATION AS REQUIRED:

WELL NO. 16

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
☒ Check if no Drill Stem Tests Run.				
Soil & clay	0	7		
Sand rock	7	14		
Clay & sand rock	14	29		
Lime	29	30		
Shale w/lime streaks	30	47		
Lime	47	51		
Sandy shale	51	74		
Shale	74	88		
Lime	88	104		
Shale	104	114		
Red Bed	114	139		
Shale	139	161		
Lime	161	171		
Shale	171	175		
Lime	175	177		
Shale	177	193		
Water sand	193	249		
Shale	249	323		
Lime	323	325		
Shale	325	330		
Lime	330	335		
Shale	335	481		
Lime	481	500		
Lime & shale	500	509		
Lime	509	541		
Shale	541	552		
Lime	552	558		
Shale	558	570		
Lime	570	636		
Shale	636	742		
Soft white lime	742	780		
Shale	780	796		
Lime	796	798		
Sandy shale	798	845		
Continued				

If additional space is needed use Page 2, Side 2

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	9 7/8	7 5/8	26.4	71	Class A	38	2 % CaCL
Casing	6 3/4	4 1/2	9.5	1725	50-50 Posmix	190	10% salt 2% gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			19	3 1/2" A1	1625-1634
Size	Setting depth	Packer set at			

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

1-27-25 p1
SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Continued				
Lime w/shale	845	858		
Lime	858	880		
Shale	880	883		
Lime	883	886		
Shale	886	906		
Lime	906	912		
Shale	912	925		
Lime	925	947		
Shale	947	952		
Lime	952	956		
Shale	956	964		
Lime	964	988		
Shale	988	991		
Lime	991	999		
Shale	999	1002		
Broken lime	1002	1005		
Lime	1005	1021		
Shale	1021	1028		
Lime	1028	1031		
Shale	1031	1071		
Lime	1071	1074		
Shale w/lime	1074	1084		
Shale	1084	1092		
Lime	1092	1093		
Shale	1093	1120		
Lime	1120	1128		
Lime	1128	1136		
Shale	1136	1150		
Lime	1150	1166		
Lime & shale	1166	1173		
Sandy shale	1173	1230		
Lime 40'	1230	1262		
Shale	1262	1281		
Lime 20'	1281	1299		
Shale	1299	1306		
Lime 5'	1306	1312		
Shale sand faint odor	1312	1344		
Shale	1344	1350		
Shale w/lime	1350	1353		
Shale	1353	1368		
Lime	1368	1370		
Shale	1370	1377		
Lime	1377	1379		
Shale	1379	1383		
Sandy shale	1383	1396		
Shale	1396	1401		
Sand oil show	1401	1407		
Shale	1407	1419		
Shale	1419	1484		
Sandy shale	1484	1507		
Shale	1507	1578		
Sandy shale odor Burgess	1578	1601		
Shale	1601	1616		
Lime	1616	1618		
Sandy lime good show	1618	1634		
Lime	1634	1731 T.D		