



OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

December 22, 1982

Rebel Resources, Inc.
c/o Vic Leis
Box 223
Yates Center, Kansas 66783

Gentlemen:

Attached hereto are the results of tests run on the rotary core taken from the Eck Lease, Well No. 9, located in Section 24, T-27S, R-13E, Wilson County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and submitted to our laboratory on December 20, 1982.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES


Sanford A. Michel

SAM/rmc

5 c to Yates Center, Kansas

OILFIELD RESEARCH LABORATORIESLOGCompany Rebel Resources, Inc. Lease Eck Well No. 9Depth Interval,
FeetDescriptionSQUIRREL SANDSTONE

1083.0 - 1083.9	Gray slightly sandy shale.
1083.9 - 1085.6	Brown sandstone.
1085.6 - 1088.1	Brown slightly micaceous sandstone.
1088.1 - 1088.7	Brown shaly sandstone.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Company Rebel Resources, Inc. Lease Eck Well No. 9

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A. Ft.	Permeability, Millidarcys
			Oil	Water	Total		
1	1084.5	18.5	32	38	70	459	44.
2	1085.4	17.9	47	33	80	653	27.
3	1086.3	16.9	42	37	79	551	21.
4	1087.5	16.9	45	44	89	590	11.
5	1088.3	15.7	73	19	92	889	3.4