

LOG

COPY

Company Bonanza Energy Corp. Lease North McCune Well No. 7BARTLESVILLE SANDSTONE

Depth Interval, Feet	Description
1120.0 - 1122.0	Shale and sandstone, gray and light brown, laminated.
1122.0 - 1122.5	Sandstone, brown.
1122.5 - 1122.8	Shale, gray with widely scattered light brown sandstone partings.
1122.8 - 1123.0	Sandstone, light grayish brown, shaly with scattered shale and mica partings.
1123.0 - 1124.1	Sandstone, brown with scattered shale partings.
1124.1 - 1124.6	Shale, gray with widely scattered light brown sandstone partings.
1124.6 - 1126.2	Sandstone, brown with widely scattered shale and mica partings and inclusions.
1126.2 - 1126.5	Shale, gray with widely scattered light brown sandstone partings.
1126.5 - 1126.8	Sandstone, brown with scattered shale and mica partings.
1126.8 - 1127.2	Shale, gray with scattered light gray sandstone partings.
1127.2 - 1127.8	Sandstone, brown with widely scattered shale and mica inclusions.
1127.8 - 1128.4	Shale and sandstone, gray and light gray, laminated.
1128.4 - 1128.8	Limestone, light gray, sandy with scattered shale partings.
1128.8 - 1129.5	Sandstone, brown with widely scattered shale and mica partings and inclusions.
1129.5 - 1131.3	Shale, gray with widely scattered light brown and light gray sandstone partings.

Company Bonanza Energy Corp. Lease North McCune Well No. 7BARTLESVILLE SANDSTONE (Continued)

<u>Depth Interval, Feet</u>	<u>Description</u>
1131.3 - 1131.6	Sandstone, brown, shaly.
1131.6 - 1132.0	Shale, gray with widely scattered light gray and light brown sandstone partings.
1132.0 - 1134.6	Sandstone, brown with widely scattered shale and mica inclusions.
1134.6 - 1135.0	Sandstone and shale, brown and gray, laminated.
1135.0 - 1136.0	Sandstone, brown with widely scattered shale and mica partings.
1136.0 - 1136.5	Shale, gray with widely scattered light gray sandstone partings.
1136.5 - 1137.9	Sandstone, brown with widely scattered shale and mica inclusions.
1137.9 - 1138.1	Sandstone and shale, light brown and gray, laminated.
1138.1 - 1138.6	Sandstone, light grayish brown, shaly with scattered shale and mica partings.
1138.6 - 1138.9	Shale and sandstone, gray and light brown, laminated.
1138.9 - 1139.8	Sandstone, light brown with widely scattered shale and mica partings.
1139.8 - 1140.0	Sandstone, brown with widely scattered shale and mica inclusions.
1140.0 - 1141.3	Shale, gray with widely scattered light gray sandstone inclusions.
1141.3 - 1145.8	Sandstone, brown with very widely scattered shale and mica partings and inclusions.
1145.8 - 1146.3	Sandstone, dark grayish brown, shaly, slightly carbonaceous.

Company Bonanza Energy Corp. Lease North McCune Well No. 7BARTLESVILLE SANDSTONE (Continued)

Depth Interval, Feet	Description
1146.3 - 1146.7	Sandstone, brown with scattered shale partings.
1146.7 - 1147.2	Shale, gray with scattered light brown sandstone partings.
1147.2 - 1147.7	Sandstone, brown with widely scattered shale and mica partings.
1147.7 - 1149.0	Sandstone, grayish brown, shaly, slightly carbonaceous with widely scattered shale and mica partings.
1149.0 - 1150.2	Sandstone, grayish brown, very shaly with scattered shale and mica partings.
1150.2 - 1153.0	Sandstone, grayish brown with widely scattered shale and mica partings and inclusions.
1153.0 - 1153.6	Sandstone, grayish brown, shaly with scattered shale and mica inclusions.
1153.6 - 1154.1	Sandstone, brown with widely scattered shale and mica inclusions.
1154.1 - 1154.9	Shale, gray with scattered light gray sandstone partings.
1154.9 - 1155.9	Sandstone, light grayish brown, very shaly with scattered shale and mica partings.
1155.9 - 1159.8	Sandstone, brown with very widely scattered shale and mica partings.