



OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

August 28, 1981

Jackson Meyers
1420 South Santa Fe
Chanute, Kansas 66720

Gentlemen:

Attached hereto are the results of tests run on the rotary core taken from the Adelgren Lease, Well No. 1-A, located in the Northeast $\frac{1}{4}$ in Section 36, T-27S, 16E, in Wilson County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and was submitted to our laboratory on August 26, 1981.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Sanford A. Michel
By B.L.

Sanford A. Michel

SAM/kas

5 c to Chanute, Kansas

OILFIELD RESEARCH LABORATORIES

LOGName Jackson Meyers Lease Adelgren Well No. 1-ADepth Interval,
FeetDescriptionBARTLESVILLE SAND

973.0 - 974.0	Grayish light brown very shaly sandstone.
974.0 - 979.0	Light brown sandstone.
979.0 - 980.0	Grayish light brown very shaly sandstone.
980.0 - 983.8	Brown sandstone.
983.8 - 984.8	Brownish black slightly calcareous carbonaceous very shaly sandstone.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Company Jackson Meyers Lease Adelgren Well No. 1-A

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	973.7	10.2	8	83	91	63	0.23
2	974.6	17.1	19	39	50	252	12.
3	975.5	16.5	17	37	54	218	24.
4	976.5	13.7	23	48	71	245	13.
5	977.5	15.9	24	38	62	296	39.
6	978.5	16.8	36	32	68	469	37.
7	979.4	13.5	28	46	74	293	1.6
8	980.5	15.0	36	43	79	419	12.
9	981.6	17.4	23	53	76	310	25.
10	982.5	17.1	30	46	76	398	59.
11	983.5	14.7	34	40	74	388	0.48
12	984.4	14.7	42	31	73	479	0.46