

State Geological Survey

WICHITA, BRANCH

KANSAS DRILLERS LOG

API No. 15 — 205 — 20,407
County Number

Operator

Brandes Oil Company

Address

P. O. Box 707 Chanute, Kansas 66720

Well No.

Lease Name

#2

Rubow

Footage Location

1230' FNL & 600' FEL

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

J-J Drilling

Geologist

Spud Date

3/8-78

Total Depth

1180

P.B.T.D.

Date Completed

3/15/78

Oil Purchaser

McClaskys


S. 6 T. 27 R. 17 E

Loc. 1230' FNL & 600' FEL

County Wilson

640 Acres

N



Locate well correctly

Elev.: Gr.

DF

KB

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	9"	6 1/4"		25'	Portland	5	
Casing	4 7/8	2"		977	Portland	190	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			9	1 11/16	926/930
TUBING RECORD					
Size 1"	Setting depth 920	XXXXX Set at S.N 918			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Oil Frac 30 Sx 12/30 Sand	926/930
10 Sx 10/20 Sand	
80 Gal 15% Acid 100# Water Gel	

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
	Pump
RATE OF PRODUCTION PER 24 HOURS	Oil 2 bbls. Gas MCF 10 bbls. Water Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval(s)
Vented	Cattleman

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

State Geological Survey
WICHITA, BRANCH

3	Lose Rock	3
3	Clay	6
34	Shale	40
1	Lime	41
61	Shale	102
15	Lime	117
58	Shale Sandy	175
45	Lime	220
22	Shale	222
3	Coal	225
3	Shale	228
12	Sand Gray	240
10	Lime	250
7	Sand	257
15	Shale	273
5	Lime	278
20	Shale	298
14	Sandy Shale	312
68	Lime	380
7	Shale	387
5	Lime	392
8	Sandy Shale	400
102	Lime	502
71	Sandy Shale	573
17	Shaley Lime	590
9	Shale	599
12	Lime	611
91	Shale	702
21	Lime	723
3	Shale	726
4	Lime	730
23	Black Slate	753
7	Gray Sandy Shale	760
18	Lime Brown	778
4	Shale	782
5	Lime	787
2	Shale	789
1	Coal	790
15	Shale	805
4	Lime	809
2	Sand	811
3	Sand Show of oil	814
15	Sand Broken Show of oil	829
5	Sandy Shale Black Sand	834
23	Shale Black Limey	857
2	Lime	859
48	Shale Sandy	907
2	Sand Show of oil	909
19	Broken Sand and Shale	924
13	Sand Good show of oil	937
53	Sand Water Light Show of oil	990
40	Sandy Shale	1030
15	Broken Sand Light Smell of oil	1045
25	Shale Sandy	1170
10	Chert and Lime	1180