

WELL RECORD

Well No. W-40 Farm Barker Producer Belleair Oil Corporation
 Location Sec. 4 Twp. 27 Rg. 18E
 Elevation _____ State Kansas County Neosho
 Kind (Oil, Gas, Water, Dry Hole) _____ Contractor Herring & Davis
 Producing formation _____ Top _____ Bottom _____
 Shot with Nitro _____ lbs. 20 from 736 to 744
 Packer settant 710.6 Kind Gas Size 2 x 6 1/2 x 12"
 Liner _____ from _____ to Perforated from _____ to _____

Thick- ness	Strata	Depth	
	Soil	4	Total Depth 750'
10	Clay	14	
3	Gravel	17	Casing 7" at 22'
2	Shale & Gravel	19	
13	Lime	32	Casing at
12	Shale	44	
1	Shale Black	45	Casing at
71	Lime	116	
5	Shale Black	121	Additional Information
6	Lime Pink	127	
4	Sand Light		Packer set at 710.6, seat-
	oil show	131	nipple at 727', 8 burlape
20	Lime	151	sacks on packer, 25 sacks
4	Shale	155	1 day cement on top of
30	Lime Brown	185	packer.
2	Shale Dark	187	
9	Lime Brown	196	Try to set gas packer at
	Sandy		736' but would not hold,
151	Shale Grey	347	ran rag packer and this
	Sandy		packer would not hold. Ran
4	Shale Black	351	another gas packer and set
30	Lime	381	it at 710.6.
27	Lime & Shale	408	
18	Sand w/Shale	426	Well not cored.
9	Lime	435	
40	Shale	475	Below packer, Close nipple,
27	Lime & Shale	502	cage, collar, 2 x 8 Nipple,
38	Shale Dark	540	seating nipple, collar,
17	Lime	557	2 x 12 Nipple.
6	Shale	563	
4	Lime	567	Well Drilled Jan. 17, 1953
88	Shale	655	Well Started Jan. 13, 1953
1	Lime	656	
51	Shale Dark	707	
8	Shale Sandy	715	
10	Sand & Shale	725	Odor
8	Sand Gas	733	
3	Sand	736	Oil Show
14	Sand	750	Good Oil

6-17-54 Pipe unscrewed at 340 ft. 40' of new 2" Plain pipe put in for replacement.

Plugged w/ Leffler Plugging Packer Tubing Salvaged after being shot off

727
120
607
650ft