

W-2X

WELL RECORD

Well No. ~~C.O.#1~~ Lease Corbett Sec. 13 Township 27-S Range 19-E

Location _____ County Neosho State Kansas

Date Completed April 29, 1955 Drilling Contractor Carl Bernd

Casing _____ at _____ Casing _____ at _____ Casing _____ at _____

Original T.D. _____ Cored _____ T.O.S. _____

B.O.S. _____ Net Feet of Pay _____ Plug Back _____

Cement On Packer 20 1/2 sacks Seating Nipple 12' feet off bottom

Packer 737.6' Kind Belt Size 4 7/8

Tubing _____ Liner _____ Anchor Below Packer _____

1" Tubing _____ Rods _____ Pony Packer _____

Barrel _____ Kind _____ Size _____

Type Unit _____ Motor _____ Well Power _____

Initial Production: BOPD _____ BHPD _____ Bbls. Total Fluid _____

Method of Completion:

Well cleaned out to top sand and on down to lower sand, making total depth of 796.5'. Ran 4 7/8 belt packer with 8 gunny sacks on it, ran down in old shot hole in upper sand and pulled up, packer set at 737.6'. Pumping equipment fixed with 46.9' 10 round thread. Pipe below packer 23.4' of 2" perforated every 12 inches - 1st jt. below packer, seating nipple in 4 way tee, 12 feet off of bottom, well showed some oil and gas. 20 1/2 sacks 1 day cement ran thru 1" pipe.

786.2' 10 Round 2" used.

Work Over Operations and Remarks:

May 6, 1955 - Ran in 1" used pipe (light) and rebuilt insert bbl.

~~Converted to 1 1/2" pipe~~