

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


2-27-2E

Company- H. H. BLAIR
Farm- Ketteman No. 2

SEC. 2 T. 27 R. 2E
SW SE SW

Total Depth. 3285'
Comm. 5-10-61 Comp. 5-26-61
Shot or Treated.
Contractor. Red Drlg. Co.
Issued. 7-8-61

County Sedgwick
KANSAS



Elevation. 1360' DF

Production. Dry

CASING:

8 5/8" 141' cem w/150 sx.
5 1/2" 3265' cem w/75 sx.

Figures Indicate Bottom of Formations.

cellar	4
clay	10
shale	30
shale & lime	90
lime	141
lime & shale strks	290
lime & shale brks	445
lime & shale	570
shale & lime	725
shale & lime strks	810
shale & lime	862
shale & lime strks	1840
lime & shale	1980
shale & lime	2073
lime & shale	2295
shale & lime	2410
lime & shale brks	2513
lime & shale	2695
shale & lime	2840
lime & shale	2872
lime & chert	2939
lime - cherty lime	2977
lime - chert	3002
lime	3110
shale - lime	3131
shale	3162
lime	3169
lime & shale	3206
sandy shale	3241
sand & shale	3264
sand	3284
lime	3285
Total Depth	

TOPS: SCOUT	
Lansing Lime	2050
Kansas City	2419
Mississippi	2872
Kinderhook	3122
Viola	3168
Upper Simpson	3204
Lower Simpson	3264
Arbuckle	3284