

4-27-2E


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- W. L. HARTMAN
Farm- Rowland No. 1

SEC. 4 T. 27 R. 2E
CN/2 N/2 SW

Total Depth. 3401
Comm. 6-12-52 Comp. 7-1-52
Shot or Treated.
Contractor. Morrison Drlg Co., Inc.
Issued. 8-30-52

County Sedgwick
KANSAS



Elevation. 1399

Production. Pmp 25 bbls

CASING:

8" 85'
5" 3401'

Figures Indicate Bottom of Formations.

cement	32 -85
shale	155
shells, lime	225
lime, shale	640
lime, shells	700
lime, shale	790
lime, shale brks	945
shale, shells	1245
lime, shale	1905
shale, shells	1920
lime, shale	1931
shale	2130
lime	2257
lime w/shale strks	2295
lime	2336
shale, lime strks	2380
shale	2492
lime	2651
lime, shale strks	2823
shale, lime	2899
shale	2926
Diamond Coring	2926--2986
lime	3007
lime cherty	3042
lime	3210
shale	3255
Diamond Coring	3255--3391
lime	3401
Total Depth	Rotary

Tops: Scout	
Heebner	1924
Lansing	2135
Kansas City	2492
Marmaton	2656
Miss.	2939
Kinderhook	3210
Misener	3262?
Hunton	3262?
Maquoketa Shale	3270
Viola	3275
Simpson	3288
Arbuckle	3376